



ZEBRA²

USER GUIDE



VERSION 2.9.4

17. SEP 2024

Table of Contents

Introduction	5
About Zebra2	5
Quick and Easy Tutorial	7
User Interface	10
Basic Operation	10
Upper Bar	11
Temporary GUI settings	12
Synthesis Window	12
Main grid	13
Lane Mixer	14
Performance Window	15
Lower Bar and Lower Pane	16
Preset Browser	17
Overview	17
Directory Panel (folders)	18
Presets Panel (files)	20
Drag & Drop	22
Preset Info Panel	23
Installing Soundsets	23
Preset Tagging	24
Search by Tags	25
Search by Text	27
Global Settings	29
PITCH	29
GLIDE	29
VOICES	29
MODE (voice mode)	30
MICROTUNING	30
SWING	30
Generators	31
OSC main panel	31
PHASE	32
OSC FX	32
List of spectral effects	33
MIXER	34

OSC Lower Panel.....	35
OSC Wave Editor	38
GeoMorph & SpectroMorph	38
GeoBlend & SpectroBlend.....	40
FMO main panel.....	42
FMO lower panel.....	43
Noise	44
VCF	45
XMF.....	47
Comb	49
SB (Sideband)	52
Shape.....	52
Distortion.....	53
Ring	55
Mix	55
Fold	56
Modulators	57
List of Modulation Sources	57
Modulation Matrix	58
ENV	59
MSEG.....	62
LFO	64
LFOG.....	66
MMap.....	67
MMix	69
Outputs and Effects	70
The FX Grid	70
Modulation FX.....	71
Delay	72
Reverb.....	73
Compressor	74
EQ	75
NuRev	76
Performance	77
Arpeggiator / Sequencer Programming	77
Hands-on tutorial	77
Selectors.....	78
Step parameters	79
XY Pad Programming.....	80

Configuration	82
About MIDI CC.....	82
MIDI Learn.....	83
MIDI Table	84
Preferences	85
Tips & Tricks	87
Motion viewer for modulators.....	87
Spectralize	87
Modulation inverter	88
Absolute value	88
Vibrato under control	88
More MSEG points	88
Zebrify	89
Introduction.....	89
MIDI.....	90
Input.....	91
Input Mixer	91
Envelope Detector	91
Pitch Detector.....	93
ZRev	94
Modulation Target Lists	95
Generators	95
Modulators.....	101
Global.....	103
Effects	103
Flow Diagrams	109
Delay Modes.....	109
XMF Modes.....	111
FX Grid.....	112
NKS	113
Troubleshooting	114

Introduction

About Zebra2

Zebra2 is a wireless modular synthesizer. Designed for flexibility, ergonomics and low CPU hit, Zebra2 has an excellent reputation for consistently great sound quality. Zebra2 is the weapon of choice for composers and musicians who need an uncompromising workhorse synth – practically all parameters are valid modulation targets.

Zebra2 modules only appear while they are in use: Add an oscillator to the patching grid and it will appear on the left, use an LFO for anything and it will appear on the right. After a little practice you will find programming Zebra2 very comfortable and lightning fast. Which in the end translates to... more fun!

Installation and updates

Go to the [Zebra2](#) web page and download the latest installer for your system (macOS or Windows). Unzip the compressed file, open the Zebra2 folder and start the installer.

Zebra2 works in demo mode for a while before it cycles through a series of 5 notes instead of the correct ones. Register your copy by clicking on Zebra2's data display and selecting the first entry, *enter serial number*. Then unload and reload Zebra2 to make 100% sure that the registration process is complete.

During installation, files are written to the following locations by default (Windows users please note that these have changed since previous Zebra versions):

macOS

Presets (local)	<i>MachHD/Library/Audio/Presets/u-he/Zebra2/</i>
Presets (user)	<i>*YOU*/Library/Audio/Presets/u-he/Zebra2/</i>
Preferences	<i>*YOU*/Library/Application Support/u-he/com.u-he.Zebra2...</i>
Themes	<i>MachHD/Library/Application Support/u-he/Themes/</i> (skin folders)
Module presets	<i>MachHD/Library/Application Support/u-he/Zebra2/Modules/</i>
Microtuning	<i>MachHD/Library/Application Support/u-he/Tunefiles/</i>

Windows

Presets (local)	<i>C:\Users*YOU*\Documents\u-he\Zebra2.data\Presets\Zebra2\</i>
Presets (user)	<i>C:\Users*YOU*\Documents\u-he\Zebra2.data\UserPresets\Zebra2\</i>
Preferences	<i>C:\Users*YOU*\Documents\u-he\Zebra2.data\Support\</i> (*.txt files)
Themes	<i>C:\Users*YOU*\Documents\u-he\Zebra2.data\Support\Themes\</i>
Module presets	<i>C:\Users*YOU*\Documents\u-he\Zebra2.data\Modules\</i>
Microtuning	<i>C:\Users*YOU*\Documents\u-he\Zebra2.data\Tunefiles\</i>

To uninstall everything (including Zebralette, Zebraify and Zrev), delete all the above **except** the *Themes* and *Microtuning* folders, especially if they are used by other u-he plug-ins.

Online resources

For downloads, news and support, go to our [website](#)
For heated debates about u-he products, go to our [forum](#)
For friendship and informal news updates, go to our [facebook page](#)
For u-he presets (paid or free), go to our [patch library](#) (PatchLib)
For video tutorials and more, go to our [youtube channel](#)
For personal pics and a few videos, go to our [instagram page](#)
For audio demos of soundsets, go to our [soundcloud](#)

The most frequently asked question by newcomers is:

Q: *Why does Zebra go way out of tune after a short while?*

A: That's the demo mode restriction.
Right-click on the data display, enter your serial number and restart Zebra.

Team u-he 2024 (Q4)

Urs Heckmann (concepts, code)
Jayney Klimek (accounting, procurement)
Howard Scarr (sound design, user guides, grump)
Sebastian Greger (UI design, 3D graphics)
Jan Storm (framework, hardware code)
Oddvar Manlig (business development)
Viktor Weimer (customer support, sound design)
Thomas Binek (QA, betas, customer support)
Henna Gramentz (office coordination, customer support)
Frank Hoffmann (framework, browser)
Alf Klimek (studio, voiceovers)
Sebastian Hübert (media creation)
David Schornsheim (framework, CLAP)
Kay Knofe (hardware development)
Tim Fröhlich (more code)
Sadjad Siddiq (DSP code)
Petros Karagkounidis (backend development, IT admin)
Simon Schrape (web development)

Special thanks Brian Rzycki for maintaining the original PatchLib.

Quick and Easy Tutorial

Load Zebra2 into your preferred plugin host / sequencer / DAW. If you're not sure how to do this, please refer to the documentation belonging to that application.

Click on the **PRESETS** button in the upper bar. The browser shows a list of folders on the left, and all presets contained within the selected folder in the center:



The contents of the Local folder

In the folders pane, click on *Local* to open it if necessary. You should see category folders (1 Basics, 2 Leaders etc) on the left, and several presets in the main area. Click on any preset and play your keyboard. Use the up/down cursor keys to step through the others.

While auditioning the factory presets you should always try out the standard performance controls **velocity**, **pitch bend**, **modulation wheel** and **pressure**. Some presets will also react to the user-definable MIDI control changes (CC#02 and CC#11 by default).

New in version 2.9

All factory presets now include complete XY pad assignments.
Click on the **PERFORM** button and try them out.

Now that you know how to audition factory presets, it's time to familiarize yourself with the Zebra2 way of creating your own!

Right-click on the data display and select *init* (initialize), then the click **SYNTHESIS** button:



SYNTHESIS window of the 'init' preset

Only 3 modules are visible in Zebra's main programming window because *init* only uses one oscillator, one envelope and one LFO. Play your keyboard – it sounds even simpler than it looks, but this simplicity is precisely what makes *init* a great starting point for creating your own presets.

Click on the **OSC1** button in the lower bar, grab the highlighted rectangle at the bottom and move it around: All waves are sawtooth. In the **OSC1 WAVE** panel to the left, click where it says 'none' and select the **oscillator preset** *Local / Tri-Saw-Pulse* from the list. CLOSE the preset window, test the various waveforms, then set it to Wave 5 (sawtooth).

Click in the main grid somewhere below OSC1 and select **OSC2** from the list. A second oscillator appears in the lefthand pane. Turn the Detune knob in one of the oscillators up to 15 and play some notes. Take the Vibrato amount in the other oscillator up to about 30 for some extra movement. In the righthand rack, change the LFO **SYNC** mode to 0.1s and move its **Rate** down to about 60.

Now click below OSC2 and select **VCF1** (a multi-mode filter). The default is *LP Xcite*: Click there and select *LP Allround*, a more resonant lowpass. Move the Cutoff knob while playing the keyboard, then leave it at about 75. Click on the unlabeled knob on the far left, select Env2 from the list and turn that knob up to 70. Play your keyboard. In the righthand rack, adjust the ENV 2 **Attack** to 20, **Sustain** to minimum and **Velocity** to maximum.

In the upper bar, turn OUTPUT down a little so that you don't distort, then just play...

Click on the **GLOBAL** button at the far left of the lower bar. In the middle you will now see a small **effects grid**, which is used for selecting and routing effect modules.

Click on the cell below the currently inactive ModFX1 (a chorus) and choose **NuRev1** from the bottom of the menu. Reverb parameters appear in a panel to the right, replacing whatever was there before. Adjust reverb parameters **Decay**, **Size**, and especially **Dry/Wet**.

Next, add an **EQ** module below [NuRev]. An Equalizer panel appears, replacing the reverb panel. In the effects grid, click on [EQ1] and drag it up one cell: [EQ1] will swap places with [NuRev] so that the dry signal is equalized **before** the reverb instead of after it. Experiment with all effect settings (remember that clicking on a cell will reveal its panel) as well as the generator and modulator settings.



the SYNTHESIS window after following the above tutorial, with the GLOBAL panel open

Now would be a good time to learn more about Zebra's GUI – see the next section.

If you're already feeling confident you could try refining this simple preset while looking up the appropriate information in the reference chapters.

Tips: For fine control, hold down a SHIFT key on your computer keyboard before adjusting the knob. Whenever you arrive at an interesting sound, press **SAVE** in the bar at the top. By default, saved presets will land in the root of the *User* folder, but you can change this behaviour globally (see [Preferences](#)).

User Interface

Basic Operation

Although basic operation is quite intuitive, there are a few points worth mentioning...

Standard controls



Adjust values via click-and-drag, fine control by holding a SHIFT key. All knobs are either **unipolar** like *Release* in this image, or **bipolar** like *Velocity* in this image. Bipolar knobs are usually center-zero, with negative values to the left and positive values to the right.

Double-click resets a knob to its default. If your mouse has a scroll wheel, hover over any control and then roll the wheel. For finer control, hold SHIFT.

Assignable controls



Most panels include assignable controls which directly modulate important parameters. Select a source by clicking the label. Note: Both assignable controls in the VCF module affect Cutoff. What look like assignable controls in the envelopes are actually pre-attack and post-sustain (see [ENV](#)).

Parameter locking




Right-click on a control and select 'Lock'. The lock only prevents the value from changing **when you switch presets**, it does not prevent you from adjusting the value directly. To unlock, right-click again and untick 'Locked' in the menu. Example: Lock both Microtuning options to audition various presets, all with the same non-standard tuning.

Switches and the mouse wheel

Most of the rectangular buttons open drop-down menus. Like the knobs, most of them also react to mouse wheel movement (this is particularly useful in the *Arp/Seq* panel).

If your mouse wheel is rastered i.e. it has noticeable 'ticks', you should check that the *Mouse Wheel Raster* preference is switched **on** (see [Preferences](#)). This ensures that each tick will correspond to a sensible step, usually an integer.

Key Control



Experimental feature, work in progress! For various reasons we recommend using a numeric keypad a.k.a. **numpad**.

Locate this button in the upper bar, click on it, then either click on any knob or navigate using your cursor keys. Type a numerical value and confirm via Return or Enter. For negative values, type minus (-) before confirming.

Hit backspace to recall the default value. Increment / decrement integer values via (+) and (-) on the numpad. Hold shift for fine control, or option (Mac) / ctrl (Win) key for steps of 10. The system copy/paste and undo/redo shortcuts should work as expected. Video and discussion: <https://www.kvraudio.com/forum/viewtopic.php?t=611856>.

Upper Bar

At the top of Zebra's window you will see this bar:



SYNTHESIS, PERFORM, PRESETS: The buttons on the left select the 3 main windows.

DATA DISPLAY: The display has three main jobs: Firstly, it shows the preset name. You can step through the presets by clicking on the triangles to the left and right. Clicking on the name opens a list of all presets in the current directory – a convenient way to load a preset without having to open the PRESETS window. Since version 2.9.1 you can load a preset by dragging it from your desktop (or any system window) onto the data display.

Secondly, it shows the value of the parameter being edited. Watch the display whenever you need to set specific values. After about 2 seconds, it reverts to the preset name.

Thirdly, right-clicking on the display toggles between compatibility mode 2.3 (a faint '2.3' appears on the right) and the regular 2.5+. While editing 2.3 presets, remember that this mode does not support some more recent features and improvements. Also, the sound can change when you switch from 2.3 to 2.5, mainly due to the improved [XMF](#) module.

INITIALIZE: At the top of the same context menu (right-click on the display) is a simple template called *init* you can load whenever you want to program from scratch. The main grid contains an oscillator and the effects grid has an inactive Chorus/Phaser (ModFX1).

UNDO / REDO: The curved arrows to the right of the data display can be used to fix recent 'mistakes'. The number of steps in the undo buffer is limited to 30, but as you can undo a change of preset, switching presets before saving doesn't mean losing any work.

MIDI activity: This small indicator lights up whenever MIDI data is being received.

Key Control: See the previous page.

SAVE button: Stores the preset into either the currently selected folder or the 'User' folder, depending on the *Save Presets To* setting (see [Preferences](#)). To select a different folder, click on PRESETS and navigate in the directory. Click on [SAVE], give your creation a name and any details you would like to appear in the [PRESET INFO](#). Please avoid using the following characters: \ / ? % * : " > < =

Right-clicking on [SAVE] opens a menu with a choice of file formats. The recommended *h2p* option is our normal cross-platform format (editable text), while *h2p extended* includes extra readable information. The *native* option is the standard format of your system (.fxp for VST and AAX, .aupreset for Audio Units). If you have loaded Diva as VST2, you will also see the option *nksf*: See the [NKS](#) chapter towards the end of this document.

OUTPUT knob: The final volume, the sum of MAIN, BUS1 and BUS2. Controls the same parameter as the OUTPUT knob below the [FX Grid](#). Normally set to 100%, a preset's volume can be boosted up to 200% if necessary.



BADGE: Clicking on the u-he badge opens a menu containing links to this user guide, to the documents folder, to our company homepage, to our KVR support forum as well as to our presence in various social networks.


Temporary GUI settings

Right-clicking anywhere in the background of the control bar or lower pane opens a menu with options for **GUI skins** i.e. alternative designs (the current standard is *DotEight*) as well as **GUI sizes** (as percentages and as width x height in pixels).

More permanent settings are available in the [Preferences](#) page.

Synthesis Window

Click on the **SYNTHESIS** button in the upper bar...



areas of the SYNTHESIS window

Generators rack

The area to the left contains control panels for each active module in the main grid (see the next page). Generator panels can be reordered by clicking on the dividing line.

Modulators rack

The area to the right contains panels for control signals (envelopes, LFOs etc.) currently in use. Modulators are not defined in the grid, but automatically appear as soon as they are used as modulation sources. Modulator panels can also be reordered by clicking on the dividing line between them.

If the rack isn't tall enough to show all active panels, a scroll bar will appear. Right-click in an empty area of each rack to choose **auto scroll** – the rack scrolls (if necessary) to reveal the panel belonging to the module selected in the grid, or **selected on top** – the module selected in the grid moves to the top of the rack.


Note that the order of panels in the generators rack will seldom reflect the patch structure as it is defined in the grid. However, you can swap the positions of adjacent panels by clicking in the narrow space between them.

Main grid

The center of the Synthesis window is a grid consisting of four vertical **lanes**. This area is used for connecting generators together, whereby the signal flow is **top to bottom**.

To add a module, click on an empty cell and select from the list. Drag modules around the grid, deactivate via **double-click** (or Mac: **cmd+click**, Win: **alt+click**), specify input routing or remove the module via right-click. Clicking on a module will highlight the corresponding control panel in the generators pane.

IMPORTANT: Oscillators and noise generators (as well as FMOs in certain modes) do not process audio, so when placed on top of one another in the same lane, the signals are simply mixed together.



In the above example, both OSC1 and OSC2 flow into XMF1 (a filter). The XMF1 output is then mixed with (not processed by!) OSC3, and the mixture flows down lane 1. OSC4 flows down lane 2 as well as modulating XMF1 cutoff (the red arrow).


Routing between lanes

Any module can route signals between lanes. Select the source ('Input') lane for the module by right-clicking on it.

In this example, OSC1 is comb-filtered in lane 1. Both OSC1 and Noise1 are filtered by VCF1 in lane 2.


By the way: If Noise1 had been two cells further down lane 2, the Noise module would have taken its input from Comb1.

Note: For the sake of simplicity and brevity, the names of modules as they appear in the grid (which often differ from the titles of panels) are used throughout this manual.



Lane Mixer

Below the main grid is what looks like a 4-channel mixer. Indeed, this is where you adjust the pans/volumes and select envelopes as well as routing to the [FX grid](#) for each lane.



Mute

A handy mute button for each lane. In the image above, lane 2 is muted.

FX Bus Select

Selects an output for each lane:

main.....route to the lefthand lane of the FX grid (MAIN)

bus1.....route to the center lane of the FX grid (BUS 1)

bus2.....route to the righthand lane of the FX grid (BUS 2)

PAN / MOD

Pan position knob plus assignable modulation knob. Right-click on the Pan knob to toggle between *pan* and *bal* (balance) modes. Remember that **balancing** to the left means fading out the righthand channel of your stereo signal, while **panning** to the left means moving it over to the left.

Amp Envelope

Selects an envelope for each lane's amplifier.

Gate.....a simple on/off envelope, slightly smoothed

Env(n).....envelopes 1 to 4

VOL / MOD

Lane volume knob and assignable modulation knob. Modulation here *scales* the volume from 0% through 100% (center) to 200%. In the example above, the modulation wheel fades lane 1 down to silence, irrespective of the VOL value (which is about 70 here).

Note: If you want a unipolar modulation source to fade a lane in from zero it's best to use the modulation matrix instead.

Performance Window

Zebra's performance window is opened by clicking on the **PERFORM** button in the upper bar. The four X/Y pads can control up to 16 parameters each, all at the same time.



Performance window, with a different 'XY' panel selected below

- Click anywhere to jump to a new position – find different variations of the sound
- Click and drag to move smoothly – for realtime morphing
- Double-click to reset to the center

Next to each pad is a large field where you can add some text e.g. a functional description (as in the above image). To do that, double-click in the empty area.

Note: [NKS](#) hardware owners might generally prefer to use the 8 knobs instead of the pads, as the X and Y dimensions are independent. Many of the factory presets, however, are geared towards 2D control.

Clicking on the [≡] icon of each pad replaces the text field with a list of X/Y assignments. You can also make assignments here without having to open the XY panel in the lower area. Drag & drop assignment also works (as in the above image), but as the generator and modulation racks are not currently visible, this is mainly useful for assigning XY to the lane mixer and effect parameters.

For details see the section about [XY Pad programming](#) in the PERFORMANCE chapter.

Lower Bar and Lower Pane

The lower bar switches the contents of the *lower pane*:

GLOBAL	OSC 1	OSC 2	OSC 3	OSC 4	FMO	MSEG 1	MSEG 2	MSEG 3	MSEG 4	ARP/SEQ	XY 1	XY 2	XY 3	XY 4	MATRIX
--------	-------	-------	-------	-------	-----	--------	--------	--------	--------	---------	------	------	------	------	--------

GLOBAL

Output levels, the FX grid and FX panel, miscellaneous preset settings. [Go there](#)

OSC1 to OSC4

Wave Editor, oscillator load/save, miscellaneous oscillator settings. [Go there](#)

FMO

Additional settings for all 4 FMOs in a single panel. [Go there](#)

MSEG1 to MSEG4

Multi-Stage Envelope Generators. [Go there](#)

ARP/SEQ

For programming the arpeggiator / sequencer. [Go there](#)

XY1 to XY4

For programming the X/Y pads. [Go there](#)

MATRIX

The modulation matrix. [Go there](#)

Note: The lower bar and lower pane remain active in all window modes.

Preset Browser

Overview

You can load a preset in the current folder by clicking on the data display, or step through them by clicking on the arrow symbols either side of the data display...or even drag a preset file from a system window or your desktop and drop it onto the data display. But of course Zebra2 also has a powerful preset browser – click **PRESETS** in the upper bar:



Layout

Folders are on the left, presets in the center and information about the currently active preset on the right. If there is no PRESET INFO panel on the right, click on the [≡] button in the top righthand corner and tick *Show Preset Info*. The same menu also offers *Show Tags in Preset Info* – untick if you prefer not to see any tags there.

Default, init

When Zebra2 starts it checks whether *Local* contains a preset called *default*. If so, this is loaded instead of the demo sound. If you want a simple template every time you start a new instance, right-click on the data display and select *init*. Then select the *Local* folder and SAVE under the name *default*. (which does not appear in the browser). If a fresh instance doesn't load your new *default*, it probably landed in *User*, in which case you should change the *Save Presets To* in the [Preferences](#) and repeat the above.

PATCH FORMAT

At the bottom right of the browser you can specify the format in which your patches will be saved. The default is *.h2p* (recommended). To save in the plugin version's own format, select *native*. The *.h2p extended* format can include comments for each line.

SAVE ONLY ACTIVE MODULES

Unused modules will not be saved with the preset. Activating this option causes newly created modules to adopt settings from previously loaded presets.

BYPASS EFFECTS

Mirrors FX BYPASS in the GLOBAL panel. Click to temporarily deactivate all effects in the grid. This switch is **truly global** – you won't hear any effects until you deactivate it!

Directory Panel (folders)

Local and User Folders

Factory presets are sorted into 9 folders. Untagged copies of several of them are also in the Local root. After selecting a preset you can step through them using the cursor keys.

'Local' is primarily meant for factory content and MIDI Programs. You should save all your own creations to the 'User' folder (see the *Save Presets To* [preference](#)).

MIDI Programs

As well as factory presets, 'Local' also contains a special folder called 'MIDI Programs'. When the first instance of Zebra2 starts, **all** presets in that folder (up to 128) are loaded into memory so they can be selected via MIDI Program Change message. To retain the order it is important to rename them e.g. '000 rest-of-name' to '127 rest-of-name'.

'MIDI Programs' can contain up to 127 sub-folders, switchable via MIDI Bank Select messages (CC#0). Send *Bank Select* first, then *Program Change*. 'MIDI Programs' itself is bank 0, while sub-folders are addressed in alphabetical order starting with bank 1.

IMPORTANT: The content of the 'MIDI Programs' folder cannot be changed on the fly. Any changes there will only be updated after the host application is restarted.

Smart Folders

These are not regular folders, but the results of querying a database of all presets. The content is therefore dynamic; it will change whenever the underlying data changes.

Search History

A list of the most recent searches. To make them more permanent, right-click and select *Save Search...* To empty the list, right-click on 'Search History' and select *Clear*.

Saved Searches

This folder contains any 'Search History' entries that have been saved. To remove entries here, right-click and *Delete*.

Bank

These folders reference metadata about preset origin – the version of the factory library or the name of the soundset with which the preset was installed. See [Preset Info](#).

You can even create your own custom banks: Drag & drop one or more presets onto the 'Bank' folder then enter a suitable bank name into the dialogue box.

To remove Bank attributes from selected presets, either drag & drop them onto the 'no Bank' folder you will see at the bottom of the Bank list, or right-click on the Bank and select *Remove Presets from Bank*. Empty Banks will disappear.

Favourites

8 smart folders, one for each Favourite colour (1-8). See [Presets context menu](#) a few pages down. Only one Favourite colour/number can be set per preset. Presets dropped onto one of the 'Favourites' folders will be marked as such. Favourite status can be removed from all presets of one particular colour / index by right-clicking on the 'Favourite' folder and selecting *Remove All Favourite (n) Marks*.

Junk

A list of all 'junked' presets (see [Presets context menu](#) below). Presets dropped on this folder will disappear from the browser unless you make them visible via *show Junk*. The context menu also includes a function to remove the *Junk* status from all presets at once (*Remove Junk from Presets*).

Tags


Smart folders for each Categories, Features and Character tag. Presets dropped onto these folders will adopt the corresponding tag. Presets dropped onto the 'Untagged' folder will have **all** Categories, Features and Character tags removed.

Author

Smart folders for each *author name* as usually defined when presets are saved. Presets dropped onto Author folders will adopt the new name. Tip: Instead of signing each of your own creations, you could sign just one of them, then select them all and drag onto 'Author/(You)'. See the section [Internal Drag & Drop](#) a few pages down. Right click on an Author to rename globally.

Directory context menu

Right-clicking on any folder within Local or User will open this menu:



This menu is dynamic: Some of the smart folders offer extra options e.g. 'Save Search'.

Refresh

Updates the browser. Windows users should call this function whenever files have been moved, added, deleted or renamed in Explorer. Seldom necessary on the Mac.

Create New...

Insert a fresh, empty subfolder.

Rename...

Edit the folder name.

Open in Finder / Explorer

Opens a system window for the currently selected folder. If you hold down the option key (Mac) or ctrl key (Windows), this entry will change to *Show in Finder / Explorer* and the folder will be highlighted instead of opened.

Move to Trash

Moves the selected folder to the system trash. If you right click on the Junk folder, this entry will be replaced by 'Remove All Junk Marks'. If you right click on a Bank smart folder, it will be replaced by 'Remove Presets from Bank' (see Smart Folders above)

On Open Expand to


Determines which nested directories will appear in the directory whenever the GUI is loaded. The first option (none) collapses all folders, while the final option (all levels) reveals all nested folders.

Hidden Folders

Select any smart folders you don't want to see.


Presets Panel (files)

The central area shows all presets in the current directory. Click to load a preset.



Presets context menu

Right-click in the list to open a menu containing the following functions:



Mark as Favourite

Choose one of 8 'favourite' marks. The entry will be replaced with *Unmark as Favourite*. You can clear the Favourite status from all presets of one particular colour by right-clicking on the 'Favourite' smart folder and selecting *Remove All Favourite (n) Marks*. Note: As presets are referenced by name as well as their relative location, they will not retain their Favourite status when moved using Finder (Mac) / Explorer (Win) functions.

Mark as Junk / Show Junk

Instead of deleting presets you can mark them 'Junk' so they disappear from the browser. Activate *Show Junk* to display junked files and mark them with a STOP symbol.

Select All, Deselect

See 'Multiple Selection' on the next page.

Rename

Rename the most recently selected preset.

Copy to User Folder / Duplicate

The entry here depends on the status of the *Save Presets To* [preference](#) as well as on the location of the source preset(s) i.e. whether they are in the Local or the User folder. Selected presets are copied with a number appended to the name, which increments (like the *Auto Versioning* option) so that no preset can be overwritten by mistake.

Show in Finder / Explorer

Opens a system window for the right-clicked file. In smart folders only, holding down an option key (Mac) or ctrl key (Windows) replaces this entry with *Show in Browser*, which highlights the currently selected file in its original location within Zebra2's browser.

Convert to native / h2p / h2p extended / nksf

Selected presets are converted to the format specified in the [SAVE] button context menu or in the PATCH FORMAT field.

Copy/Paste

Clipboard functions. Individual or multiple presets can be copied then pasted elsewhere, even between Zebra2's browser and system windows (Finder, Explorer).

Move to Trash / Recycle Bin

Remove selected presets.

RESTORE

At the top left of the Presets panel is a [RESTORE] button which lets you audition presets to your heart's content without losing track of the one that was previously loaded.

Scan / Ready

Progress indicator for *Refresh* (see *Directory context menu* above).

Multiple selection

A block of adjacent presets can be selected via shift+click, and individual presets can be added to the selection via cmd-click (Mac) / alt+click (Win). Presets can be moved to a different folder via drag & drop (see the next paragraph). To deselect, either click on an unselected preset or choose *Deselect* from the context menu.

Drag & Drop

Internal

You can drag and drop single or multiple files from the preset panel onto any folders in the directory panel. Files dragged onto regular folders will be moved unless you hold down *option* (Mac) or *ctrl* (Windows), in which case they will be copied instead. Files dropped onto smart folders will adopt the attribute of that folder: For instance, you can set e.g. the Author or Favourite status of several presets at once.

External

To manage your preset library more comfortably you can drag presets and folders between Zebra's browser and your desktop (or any system window).

On the Mac most Finder operations will automatically update the browser. Updating might not be immediate when using multiple formats or multiple host applications, but all it usually takes is a click on the GUI or in the directory tree (which sets the focus to the clicked instance of Zebra). On Windows systems, a manual *Refresh* (see [Directory Context Menu](#)) will be required before changes to the contents of the browser appear.

Exporting smart folders

Drag a smart folder onto e.g. your desktop to create a folder containing those presets. For instance, an entry in the Search History, one of the Favourites, the 'Drums' category (includes sub-folders), all presets with the 'Duo' feature, or an Author...

Exporting favourite / Junk status

You can export Favourites, either all at once or individually. Shift+click and drag the 'Favourites' folder onto the desktop to create a file called *Favourites.uhe-fav*. Similar for sub-folders: If you shift+click and drag e.g. 'Favourites 5', this will create a file called *Favourite 5.uhe-fav*. Such files can be imported into Zebra's browser on a different computer (for instance), via drag & drop onto or anywhere within the Favourites folder.

Note: Importing *.uhe-fav* files from another computer will only work 100% correctly if all preset names and locations are identical on both computers!

Note for Windows users

According to Microsoft, drag & drop will only work between applications with the same rights (i.e. both admin or both normal) for security reasons. If the host was started using the "run as admin" option, drag & drop functionality will be limited: You can still drag objects between plug-ins, or from the plugin into system windows e.g. your desktop. However, attempts to drag & drop anything into the plug-in from outside the host will fail. This applies to presets, folders, favourites, *.uhe-soundset* files or indeed anything that can be dropped onto the plug-in GUI.

Preset Info Panel

The panel to the right shows information about the selected preset. If you can't see this panel, click on the triple bar [≡] button in the top right corner and tick *Show Preset Info*:

- ✓ Show Preset Info
 - ✓ Show Tags in Preset Info

Below the preset name you should see its path (from /Local or /User), the Bank and the Author. DESCRIPTION and USAGE text is entered immediately before saving a preset. CATEGORIES, FEATURES and CHARACTER are the tags for the currently selected preset. You can remove or add tags directly here (see [Tagging via Preset Info](#) below)...

Installing Soundsets

All soundsets that we distribute ourselves will have the extension *.uhe-soundset*, and third parties are encouraged to use this format for their own commercial soundsets (for details please contact our support team).

Standard Method

To install, simply drag & drop the *.uhe-soundset* file into Zebra2 – anywhere will work. The soundset folder should appear within the 'User' folder. If a soundset with the same name already exists there, any modified files will be backed up and the location of the backup file will be displayed.

Alternative Method

Soundsets in *.uhe-soundset* format can also be installed by clicking on the u-he badge, selecting *Install Soundset...* and navigating to the desired file.

Regular Folders

Folders containing Zebra2 presets can be manually copied or moved into the 'User' folder. You might have to refresh the browser (see [Directory context menu](#)) before they appear there. A refresh is generally necessary in Windows but not in macOS.

Note: As *.uhe-soundset* files are basically ZIP-compressed folders, you can rename them i.e. replace the long file extension with 'zip', then extract the presets and documentation.

Preset Tagging

“Tags” are elements of metadata, information that you can add to presets so that they can be found more easily.

Tags are updated automatically – clicking on the [SAVE] button isn’t required! The main advantage is that presets don’t have to be saved every time you edit a tag. The main caveat is that you should only edit tags after saving your preset.

For instance, if you decide to edit tags while creating a 2nd version of an existing one, please remember that you are actually changing the tags in the original preset!

The Tagging Window

Right-click on the [SAVE] button and select *Tag this patch*:

Category		Features	Character	
Bass	Acoustic	Mono	Bright	Dark
Pads	Analogue	Poly	Constant	Moving
Leads	Digital	Duo	Clean	Dirty
Keys	Dist+LoFi	Chord	Soft	Aggressive
FX	E-Bass	BPM	Phat	Thin
Drums	FX Bass	Comb	Natural	Synthetic
Seq+Arp	Plucks	OscSync		
Other	Rhythmic	RingMod		
	Sub	FM		
	Sync	Dry		
	Synth	Modulated		
	Vocal	Percussive		
		Soft Attack		
		Slow Release		
		Glide		

Category describes a preset by analogy to instrument types or typical usage, and each has a more or less appropriate set of subcategories. *Features* are technical classifications, and *Character* tags are pairs of opposites from which you can choose just one. When you are finished, click on the **X** at the top right of the window.

Tagging via Preset Info

In the PRESET INFO panel, right-click on the *Category*, *Features* or *Character* and select or unselect tags in the context menu. If you right-click on an individual tag, the first option in the menu becomes *Remove Tag*...


The function *Create Search from Tags* finds all presets with the exact same set of tags. Tip: This function can be used to locate differently named duplicates.

Tagging via Smart Folder

You can tag presets by dragging them onto any of the *Tags* subfolders in the directory. To remove all tags from presets, drag and drop them onto the *[no Tags]* subfolder.

Search by Tags

Click on the TAGS tab to open this view. The buttons here let you set up search criteria according to existing tags with just a few mouse clicks:



Below the Search field are 4 sets of buttons (CATEGORIES, FEATURES, CHARACTER and FAVOURITES). The first 3 correspond to the tags in the tagging window (see the previous page), while the bottom row lets you find presets you have tagged as *Favourites*. Clicking on the [^] icon to the right of each heading hides the options for that set of tags.

Categories and Subcategories

Here are a few bullet points to get you started. Especially for Category tags, following a step-by-step tutorial is much easier than studying a full technical description. Try these:

Each Category has its own set of subcategories. Not selecting a subcategory here means “show me presets tagged with **any** subcategory”. Click on [Leads]...

You can select multiple categories without specifying a subcategory if you hold **cmd** (Mac) or **alt** (Windows) while clicking on the category. Try that with the [Keys] button. The number of hits increases dramatically.

Selecting a subcategory (e.g. [Bass]) with the same name as the main category means “show me all presets in the *Bass* category that do not have any subcategories defined”.


Complete category+subcategory tags appear below the subcategories as buttons with ‘off’ switches [X] so that you can add other main categories by simply clicking on them.

Search by Tags Tutorial

- Click on the DIRECTORY tab, right-click on the Search History smart folder and select *clear*. Double-click on *Local/3 Fillers* to restrict the scope of the search to that folder. Instead of preset folders, the selected path appears below the Search field.
- Click on the TAGS tab. In the Categories, select [Leads]. Subcategory buttons appear and the preset window is updated to list all presets in *3 Fillers* that are tagged as [Leads]. In this case there is only one, namely *HS Dom7Plus*.
- Now click on [Keys]. The [Leads] category is switched off, and the preset window is updated to list all presets in *3 Fillers* that are tagged as [Keys]. There are quite a few of those! Note that you haven't specified a subcategory yet.
- Hold down the cmd (Mac) or alt (Win) key and select the [Leads] category again. The previously selected [Keys] button remains highlighted and the list includes the preset *HS Dom7Plus* again – it shows all presets in the *3 Fillers* folder that have either [Leads] or [Keys] category tags, disregarding any subcategories.
- Click on the DIRECTORY tab: The text *#Leads:* #Keys:** appears in the editable field, as well as in the Search History followed by the number of presets that were found. The colon symbol ':' functions as a separator between Category and Subcategory, while the star (*) means "any Subcategory, even none".
- Click on the TAGS tab. Select the [Pads] category without holding cmd/alt: the [Leads] and [Keys] tags are removed from the search. Now select [Dist+LoFi] as subcategory. The result is a list of all presets in the *3 Fillers* folder that have the *#Pads:Dist+LoFi* tag. Immediately below the subcategory options you will see the complete tag in the form [Category:Subcategory|X]. Clicking on the X here would remove the tag, but don't do that right now...
- Instead, let's widen the scope by including another subcategory: Click on [Vocal]. The [Dist+LoFi] tag remains selected and the list is updated to presets which have either of those tags. Click on [Dist+LoFi] again and the tag search will find just one preset – the only one tagged as [Pads:Vocal] in the *3 Fillers* folder.
- Click the [Leads] category. Below the subcategories, the [Pads:Vocal] tag remains in place because it is complete (Category with Subcategory). Check the tags in PRESET INFO by clicking on the two presets in the list: they will include a *Pads:Vocal* tag or a *Leads* tag (with any or no subcategory), or both.
- Click on the DIRECTORY tab. The text *#Leads:* #Pads:Vocal* appears in the Search field as well as the Search History smart folder. If you are feeling adventurous, you can try editing the characters in the Search field – after hitting Return, the results will be updated accordingly.
- To the left of the grey search path is an 'up' [^] symbol. Click on this to exit the current folder, which in this case changes the search path from *Local/3 Fillers* to the *Local* root. The list now includes more presets because the range of the search spans all of *Local*.
- Another click on [^] expands the scope to the entire preset library i.e. */Local* and */User*. Note that clicking on the [X] symbol to the right of the search path will exit any subfolder.
- Repeat the above a few times if necessary – you'll soon get the hang of it!

Search by Text

The **Search** field lets you find presets according to a string of characters i.e. text. If you remember that the preset you're looking for has the word "*clock*" in either its name or its description, simply enter *clock* into the Search field and hit Return...



Search normally looks into the preset name, author, DESCRIPTION and USAGE (see the PRESET INFO panel). Searches are not case-sensitive and quotes are not required unless you want to include spaces between words.

If you want to restrict the search to a particular path e.g. *Local/04 Pianoids*, double click on the *04 Pianoids* folder. This path appears below the Search field instead of the preset folders. You will only see smart folders plus any subfolders within the specified path.

The [^] button to the left moves the search path up one level (in this case to */Local*). The [X] button to the right sets the search path to include all Zebra2 presets (i.e. *Local* and *User*), and the regular preset folders reappear.

Try it: Enter three or four letters then hit *Return*. For instance, *star* would find all files containing the text string *star* (e.g. *mustard* or *starters*). Entering "*star wars*" (with the quotes!) would find e.g. *Battlestar Warsaw* if such a preset existed.

Syntax

Scope

You can limit the search to just the preset name or parts of INFO by using *name*, *author*, *desc* (*description*) or *use* (*usage*) followed by a colon. For instance, *author:the* finds all presets by authors whose names include 'the'. Similarly, *desc:space* will find all presets with the word *space* in the description.

An alternative syntax lets you use ? (a single letter) and * (any number of letters), but the scope *name*, *author*, *desc* or *use* must be specified, followed by '=', and logical operators are not allowed.

Logic

The AND operator specifies that presets contain both words surrounding it. AND is implicit, but can be written explicitly if you prefer: For example, *star AND wars* (or simply *star wars*) will find presets that contain both *star* and *wars*.

OR only requires that presets contain one of the words surrounding it. For example, *star OR wars* will find presets that contain *star* as well as presets that contain *wars*. Or both.

NOT excludes presets containing the following word. To find all presets that contain *star* but do not contain *wars*, enter *star NOT wars*.

Examples using regular syntax

brass OR string 'brass' or 'string' appear in the Name, Author, Description or Usage

brass string both 'brass' AND 'string' appear somewhere in the preset

use:vibrato 'vibrato' appears in Usage

"at =" aftertouch usage is mentioned in the Author, Description or Usage field
'=' is not a valid character for preset names

"hs s" ctrl #Mono All monophonic factory presets starting with an 's' that use at least one of the A / B performance controls

Examples using alternative syntax

*desc=*trin** e.g. 'string' or 'Patrington' appear in the Description

*author=*ow?e* would find "Howie", "That old Howie", but not "Howie S"

Global Settings

To open this panel, click on the GLOBAL tab in the lower bar.



Lower pane, the GLOBAL panel

PITCH

Transpose

Shifts incoming MIDI notes within a range of +/- 24 semitones.

Fine Tune

Shifts all oscillator and filter pitches by +/- 100 cents (relative to 100% keyfollow).

- Bend +

Sets pitch bend ranges independently from 0 to +/- 48 semitones.

GLIDE

Mode

timeThe duration of the glide is constant, irrespective of the note interval.

rateThe duration of the glide is proportional to the note interval.

Range

Lower values shift the beginning of the slur closer to the target note.

Glide, Glide2

A smooth pitch transition between consecutive notes. Glide affects the Key Follow modulator, so it is applied to all modules that include this parameter (OSCs, FMOs, Combs, VCFs and XMFs). Glide2 is a bipolar offset for the even-numbered modules. The modulation source KeyFol2 is the same as KeyFol, but includes the Glide2 offset.

VOICES

To prevent glitches while running CPU-intensive presets, you can reduce the maximum number of notes that Zebra2 will try to play at once: *few* = 4 notes, *medium* = 8 notes, *many* = 16 notes. Due to intelligent voice allocation, these are all approximate values.

VOICE DRIFT

If set to On, each new note is slightly detuned, emulating the imprecise pitch of classic analogue oscillators. Switch this off for “absolute” precision.

MODE (voice mode)

Remember that here is where you activate the [arpeggiator](#)!

poly.....Normal polyphonic.

retrigger.....Monophonic – each new note triggers the envelopes.

legatoMonophonic – envelopes are retriggered after spaces between notes.
Allows for more interesting musical phrasing.

arpeggiatorPolyphonic – triggers, pitches etc. are defined in the [ARP/SEQ](#) panel.

duophonicBoth low note AND high note priority. Odd-numbered OSC, FMO, Comb, VCF and XMF pitches and cutoffs follow the lowest note, while those of even-numbered modules follow the highest note.

SOFT ATTACK

Instantaneous attack times can mean audible clicks at the start of each note. Switching this on removes all such clicks. Tip: If you do want clicks (consistent ones), leave this option off, activate RESET in the oscillator panel(s) and adjust PHASE/PW.

MICROTUNING

Zebra2 supports standard .TUN microtuning tables. Literally thousands of these are available online, and most of them are free. Click the **TUNING** button, then the selector (likely to be ‘default scale’) to open a floating directory where you can choose a table. Note: This window works like the main browser, including the drag & drop functionality.

Alternatively, right-click on the selector and choose a table from the current folder. Near the top of the same menu is *Show in Finder / Explorer*, which opens a system window for the location of microtuning files... you can put more .*tun* files in there.

MTS-ESP

Zebra2 supports [Oddsound](#) MTS-ESP, a system for microtuning multiple plug-ins within a DAW environment. The freeware ‘Mini’ version is all you need to get started.

Note: MTS-ESP can be overridden by activating Zebra’s own microtuning, for instance with the .*tun* file *Default Scale*.

SWING

In most synthesizers, ‘swing’ is only applied to the timing of an arpeggiator or mini-sequencer. In Zebra2, it also affects any/all synchronized LFOs.

Time Base / Percent

Set a rhythmic basis in the popup menu then a swing factor using the knob.

Generators

OSC main panel

To state that the Zebra2 oscillators are ‘highly flexible’ would be a huge understatement. They are so powerful that the Zebra2 package includes an extra instrument called Zebralette – just one oscillator transplanted into a much simpler synth framework.



Oscillator panel with the MIXER sub-panel selected

The button next to the module label is for loading oscillator presets (see [Oscillator Preset](#)).

Switches

Stack

Selects single or polywave i.e. 2, 4 or 11 stacked oscillators. The *eleven* mode is much more than a “supersaw”, as the polywave effect can be applied to any waveform at all.

PWM

Adds an inverted copy of the waveform. Applied to a sawtooth, phase modulation creates an effect very similar to classic PWM (only the phase of the original wave is shifted around, while that of the inverted copy remains fixed). See PHASE below.

Sync

Activates oscillator-internal hard sync. See PHASE below.

Reset

Causes the oscillator to start at the same phase position each time.

Knobs

Wave

The position (index 1–16) within the waveset. Unlike the row of selectors below the wave editor, this knob lets you set intermediate values.

The knob below Wave is for wave index modulation (+/-16) – click on the label to select a source. How smoothly and precisely waves are interpolated depends on the oscillator’s [Resolution](#) setting in the lower panel. Note: The center of the waveset is actually 8.5, so a modulation amount of 7.5 from a bipolar source is enough to span the entire waveset. To reach Wave 16 from Wave 1 using a unipolar source (such as the mod wheel), set the amount to +15.

Tune

Oscillator pitch offset (+/- 48 semitones). You can hold down SHIFT for finer control, but there is also a Detune knob to the right. The knob below is for Tune modulation (+/- 48 semitones). Right-click to select a source, then turn up the amount

Detune

Detune actually has two slightly different meanings, depending on the polywave setting: In Single mode it is for fine tuning (+/- 50 cents). In Dual, Quad or Eleven modes it does not lower or raise the overall pitch of the oscillator, but spreads detuning equally. Of course you can still fine tune the oscillator via Shift+Tune.

Vibrato

The amount of pitch modulation directly from LFO1 (0 – 100). The maximum depth here is only +/- 50 cents – for deeper vibrato, click on the assignable ‘...’ control below the Tune knob and select LFO1 from the list.

The oscillators in Zebra2 may appear quite harmless, but there is a lot more than meets the eye. Apart from the extra parameters in the [lower panel](#), oscillators have 3 switchable sub-panels, PHASE, Osc FX and MIXER, selected via the buttons at the top right...

PHASE

Click on the oscillator’s **PHASE** tab:



Phase/PW

Adjusts the oscillator phase (from 0° to 180°, but you can modulate it up to 360°). Rapid phase modulation normally affects pitch, but if the PWM switch (see above) is on, the effect is similar to pulse width modulation.

Sync

Pitch offset for the oscillator’s integrated hard-sync. This classic ‘analogue’ sync adds a lot of upper harmonics.

OSC FX

Click on the **OSC FX** tab:



The oscillator waveform can be processed by a couple of **spectral effects**, which are routed in series (left > right).

To select a spectral effect, click on the **label** of an upper knob. Adjust the value and/or modulate to taste using the assignable control. Here, the *Scrambler* effect is set to zero, but is modulated by the pitch bender.

Note: When modulated, the speed and smoothness of most spectral effects DEPEND on the [Resolution](#) setting.

List of spectral effects

<i>Fundamental</i>	Adjusts the level of the fundamental. Range = -200% (inverted) to +200%. At the central position, the fundamental is inaudible.
<i>Odd for Even</i>	Even-numbered harmonics are cross-faded into odd harmonics. This results in a more 'suarish' waveform (square waves contain only odd harmonics). With negative values, the opposite applies – odd harmonics become even harmonics.
<i>Brilliance</i>	Boosts (positive) or attenuates (negative) higher harmonics, resulting in brighter or darker waveforms.
<i>Filter</i>	A combination of lowpass (negative values) and highpass (positive values) filters. Because in reality the 'filter' code only manipulates amplitudes, its slope is more than 100dB/octave.
<i>Bandworks</i>	A combined bandpass (positive) and notch filter (negative).
<i>Registerizer</i>	Boosts any octaves of the fundamental while attenuating all other harmonics, often resulting in an organ-like sound.
<i>Scrambler</i>	Similar to operator feedback in FM synthesizers: the phase of the waveform is modulated by the wave itself, creating many new overtones. If you need dirty-sounding digital oscillators, this is the one.
<i>Turbulence</i>	Periodically shuffles the harmonics at random. Even if not modulated, the speed of this effect is dependent on the oscillator Resolution . Turbulence is useful in SpectroBlend mode with only a few harmonics.
<i>Expander</i>	Expands (or contracts when negative) the spectrum. Similar to brilliance if the harmonics are distributed evenly.
<i>Symmetry</i>	Contracts the waveform towards the beginning or end of its cycle. Often sounds like pulse width modulation – and for a square wave, that's precisely what it is!
<i>Phase Xfer</i>	A variant of PD (phase distortion) synthesis. The original waveform is not output directly, but is used as the phase response of an extra sine wave – which you can hear when the value is zero.
<i>Phase Root</i>	The original wave multiplies the phase response of the sine wave.
<i>Trajector</i>	The original wave adds to the phase response of the sine wave. Like phase modulation in 'FM' synthesizers – try Trajector on a pure sine.
<i>Ripples</i>	Multiplies the waveform with a variable harmonic, resulting in quasi-resonant sounds.
<i>Formanzilla</i>	Multiplies the spectrum of the waveform with a variable harmonic, resulting in formant-like spectra with several strong peaks and troughs.
<i>Sync Mojo</i>	Simulates hard sync by contracting the time axis then writing the waveform back into wave memory.
<i>Fractalz</i>	Like Sync Mojo, except that the already contracted wave is contracted again etc.. This results in a fractal waveform with even more harmonics than Sync Mojo. Fractal structures can be found in nature.

<i>Exophase</i>	A classic 7-stage phaser is applied to the original wave. This effect is equally useful for static coloration or resonant sweeps.
<i>Scale</i>	The relative amplitudes of harmonics are scaled, either to the power of 2 (negative, softer) or 3 (positive, brighter). Results in finer resolution of quiet harmonics, so more precise control over the overtone structure.
<i>Scatter</i>	Similar to Scrambler (see above), but here the phase is modulated by itself squared (i.e. to the power of 2). An FM triangle or square from a pure sine, or absolute chaos from a sawtooth – Scatter is flexible.
<i>ChopLift</i>	Negative values raise an amplitude threshold below which harmonics are faded out (Chop). Positive values raise levels of fainter harmonics (Lift).
<i>HyperComb</i>	Adds 3 copies of the original wave to the wavetable. For positive values (only), the phases are randomly shifted, resulting in a subtle to dramatic effect similar to chorus. Even when not modulated, positive HyperComb is dependent on the value of oscillator Resolution .
<i>PhaseDist</i>	Phase distortion, as in the '80s Casio CZ series of synthesizers. The wave acts as a function for the phase of an inverse cosine. The 'amount' knob crossfades between no effect and full effect, so the most dramatic uses of this effect involve modulating Wave index.
<i>Wrap</i>	Inverts parts of the wave that extend above or below a threshold. The limits for multiple wrapping are greater with negative values.
<i>DX</i>	Same as <i>Trajector</i> (see above), but approximately 10 times stronger.
<i>Smear</i>	Blurs the spectrum in one direction (negative = down, positive = up).

MIXER

Click on the oscillator's **MIXER** tab:

Pan

Panorama shifts the stereo position to the left or right.

Volume

Oscillator output level.

Width

If the oscillator's STACK setting is *dual*, *quad* or *eleven*, this knob controls the stereo separation of the polywave. Does nothing if STACK is set to 'single'.

OSC Lower Panel

Center-stage in the oscillator's lower panel is its [Wave Editor](#). On the far left is a sub-panel containing the following elements...



Note: The OSC 1 WAVE panel allows wavetable export to Hive – see the next page!

Preset

Use this button to load or save complete oscillator templates. Left-click to select a preset from a floating window or right-click to open a context menu containing the functions *copy*, *paste*, *Save Oscillator(n) Settings* and *Show in Finder (Mac) / Explorer (Win)*. The *Copy* function can be used to transfer all settings to a different oscillator, even one in another instance of Zebra2. *Show in Finder (Mac) / Explorer (Win)* opens a system window and highlights the oscillator preset folder.

Note that all modulation assignments (e.g. Wave modulated by LFO2) ARE oscillator settings, while the settings in the modulation sources themselves are NOT. This means that an oscillator preset might not sound the same as when you saved it.

Waveform

This button selects the basic mode for the current oscillator: *Geomorph*, *SpectroMorph*, *GeoBlend* or *SpectroBlend*. All will become clear in the next few pages...



Renderer

Oscillator 'sharpness', either *soft* or *crisp*. We recommend only switching to *crisp* if you really need those extra 'spikes' and are not too concerned about aliasing.

Norm (normalization)

The output level of the generated wave is analyzed (RMS), then low-level waves are boosted so that the final level would be 0dB if Normalize were set to 100%.

High normalization values are OK for boosting most low-level waves, but please keep them lower on very spiky waves – unless of course you enjoy blasting a lot of high frequencies through your system!

Resolution


Controls the time between successive waveform calculations, ensuring that Zebra2 is still very CPU-efficient compared with other synthesizers that calculate their waveforms in realtime. The range is from 4 seconds (at 1.00) to below one millisecond (at 9.00).

High values lead to more precise transitions at the cost of higher CPU load. Low resolution can actually make transitions smoother, as intermediates are smoothly interpolated, but can introduce other unwanted effects e.g. during rapid pitch-modulation. For most purposes, the default value of 5.00 is best.

KeyS (key scale)

MIDI note to oscillator pitch, centred around the note E2. A bipolar 'KeyFol' for the oscillators. for perfect semitones, set this to 100.00.

Wavetable Creation and Export (OSC 1 only)



While developing our [Hive 2](#) synthesizer, we soon realized that Zebra2 would be a great source of wavetables, so we added the necessary functions to the lower oscillator 1 panel of the *DotEight* skin.

Whenever Zebra2 detects a significant change in the waveform, including any caused by the spectral effects but not by anything else (e.g. Sync, Stack or PWM) the waveform will be recorded into a 'frame', after which the frame index is incremented.

Saving creates a plain mono WAV file with up to 256 frames containing 2048 samples each, which can be loaded into [Hive 2](#) or wavetable-based synths such as Xfer Serum.

Quick Walkthrough

- Load *HS Ice Temple* – LFO2 is modulating oscillator 1 Wave
- Click [REC] – the button turns red
- Play any note – the grey bar starts incrementing...
- After a few seconds, click [REC] again – this pauses the recording
- Click [SAVE] – a new wavetable file will appear in the following location:

Mac *MachD/Library/Application Support/u-he/Zebra2/Wavetables/*

Win *C:\Users*YOU*\Documents\Zebra2.data\Support\Wavetables*

The default file name is *Z2 Wavetable Export -WT2048 x256.wav* (or x42 or however many frames you actually recorded). To avoid overwriting an existing wavetable with the same number of frames, double-click where it says [Z2 Wavetable Export] and edit the name before you start recording.

The Buttons

[265]	The maximum number of frames. Click and drsg up / down.
[REC]	Start or pause recording
[CLEAR]	Clear the buffer – the orange bar disappears
[SAVE]	Save the recording as a wavetable

Note: You cannot audition recorded wavetables within Zebra.

Tips and Pitfalls

You can pause, change the OSC1 waveform any way you like, then resume recording: New frames will be appended to the current wavetable.


The speed of recording often depends on the oscillator's Resolution parameter. In general the higher the resolution, the faster the buffer is filled.

You can record a series of static waveforms without pause (you don't have to hit REC again) by changing the waveform and playing a note for each frame.

Tip: pressing multiple keys at once may result in chaotic recordings. To be on the safe side it is best to use Legato [voice mode](#).

Gain Scaling

To the right is a sub-panel containing graphic controls for scaling the oscillator gain...



KEY SCALE / GAIN

MIDI note to OSC gain scaling. It can be used to balance oscillator volumes across the keyboard or even create 'keyboard splits' between oscillators. The horizontal axis is MIDI note (8 octaves) and the vertical axis is oscillator gain, independent of Volume.

VELOCITY SCALE

Velocity to OSC gain scaling: The horizontal axis is MIDI velocity and the vertical axis is oscillator gain. Again, this feature is independent of the oscillator's Volume control. Can be used for velocity cross-fades or even 'velocity switching' between oscillators.

OSC Wave Editor

The Wave Editor is where you create your own waveforms. As the editor manages up to 16 different waves per **Waveset**, it includes a **Wave Selector** bar below the editing area:



The wave selector has almost the same function as the Wave knob in the oscillator's main panel – if you adjust one, the other will move accordingly. Unlike the Wave knob, however, the selector doesn't allow intermediate values (e.g. Wave = 1.5).

Mouse operations in the Wave Selector

Some extra features that work with multiple waves...

Rearrange

- (Mac) opt + drag
- (Win) ctrl + drag

Morph or Blend

- (Mac) cmd + click on the desired target wave
- (Win) alt + click on the desired target wave

Duplicate

- (Mac) opt + cmd + click on the desired target wave
- (Win) ctrl + alt + click on the desired target wave


Context menu (right-click)

- Morph / Blend, Duplicate or Exchange this wave with the currently highlighted one

GeoMorph & SpectroMorph

Although there are four oscillator modes, only two editing methods are required. This section describes the 'Morph' waveform modes and how to edit them.


GeoMorph



A typical GeoMorph wave

GeoMorph mode lets you draw waveforms by positioning up to 32 points, and adjusting the curvature of the lines between them. Note that the first and last points cannot be deleted or moved horizontally – they define the level at 0° phase. The minimum number of points is 4, and all waves in the waveset adopt the same total number.

SpectroMorph



A typical SpectroMorph wave

Although it looks and feels like GeoMorph, SpectroMorph is a very different animal! It does not depict a waveform directly, but rather its spectrum. 1023 harmonics in the horizontal axis are scaled logarithmically for a total range of about 10 octaves. In this mode, a horizontal line spanning the width of the editor so that all harmonics have equal levels creates a bright saw wave. By the way, the example above is a bright saw (the upper horizontal line) with two wide troughs – practically a dual notch-filtered saw.

Mouse operations, GeoMorph and SpectroMorph modes

Create or remove a handle

(Mac) cmd + right-click
(Win) alt + right-click

Multiple selection

Click in the background and drag over one or more handles
Shift + click on a handle to add or remove it from the selection
To move all selected handles, click and drag one of them

Adjust curvature (left, right)

(Mac) opt + drag, cmd + drag
(Win) ctrl + drag, alt + drag


Context menu (right-click in the editor window)

insert pointcreates a new handle (appears in all waves in the waveset)
smoothadjusts all curves in the selection for minimum spikes.
linearstraightens all curves in the selection
peaksadjusts all curves in the selection for maximum spikes
distribute alladjusts the horizontal positions of all handles for equal spacing
line up selectedline up all handles with the leftmost / rightmost in the selection
clearresets all handles to minimum level
copy / pastetransfers wavesets between oscillators (also between presets)

GeoBlend & SpectroBlend

This section describes the two ‘Blend’ waveform modes, and how to edit them...

GeoBlend



A typical GeoBlend wave

A single cycle is defined by 128 columns. GeoBlend is similar to GeoMorph in that it reflects the actual shape of the wave. However, when the morph function is used or the wave index is modulated, waveforms are not morphed, they are *blended*. The main advantage of GeoBlend over GeoMorph is that waveforms can be drawn freehand.

GeoMorph wavesets can be extracted from audio sources. A few third-party utilities are available for this purpose (try googling ‘Wav2Zebra’ and ‘Blueberry Thing’), but they do require some dedication.

SpectroBlend



A typical SpectroBlend wave

The spectrum is represented by 128 bipolar columns. Similar to SpectroMorph except that it has fewer harmonics, and these are scaled linearly for a total range of six octaves.

The lower half is ‘anti-phase’, so the same harmonic in adjacent waves (e.g. 1 and 2), but with opposite phases, can cancel each other out (at exactly 1.50 in this example). This cancellation effect can be put to good use – see the oscillator preset ‘Bells Flipper’.

The main advantage of SpectroBlend over SpectroMorph is the total control over individual harmonics, including polarity. Waves are not morphed in this mode, they are blended.

Mouse operations in GeoBlend and SpectroBlend modes

draw freehand

click + drag

draw a straight line

(Mac) opt + drag

(Win) ctrl + drag

reset sections to zero

(Mac) cmd + drag

(Win) alt + drag

context menu (right-click)

blur.....softens transitions between columns

sharpen.....accentuates transitions between columns

maximize.....sets the highest column to maximum, scales the rest accordingly

copy / paste.....transfers wavesets between oscillators (even between presets)

Expand

A much larger version of the wave editor opens when you click on the vertical **[EDITOR]** button to the left of the data area. To exit, click on the same vertical button, which has been conveniently renamed CLOSE. While the wave editor is expanded, the lower pane contains a copy of the oscillator panel.

Zebralette



Making your own sounds in Zebralette (freeware, bundled with Zebra2) is the best way to become a true Zebra2 oscillator expert, as there is zero risk of being distracted by all the other Zebra2 features. Zebralette has its own user guide. Tip: You can load Zebralette programs into Zebra2.

Please note that "**Zebralette 3**", also freeware, is a different synthesizer!

FMO main panel

FMO stands for Frequency Modulation Oscillator, and this module is indeed closely related to the famous Yamaha DX7. Compare the Zebra2 preset *HS DY7 Add Pad* with the typical DX7 e-piano sounds of the 1980s, which were often layered with analogue pads.



the FMO module panel

TYPE (input mode)

FM by input: The FMO is modulated by its input, and the FM knob controls input level.

FM self (+): The FMO modulates itself for a brighter tone approaching a sawtooth. Note that FM values above 50% can produce some interesting digital noise.

RM input: The FMO is actually ring-modulated with its input. No FM here!

Filtered FM: Like FM by Input mode, except that the FM knob opens a lowpass filter instead of setting the input level (which is fixed at 100%). This results in a warmer tone.

FM self2 (+): Like FM Self (+) except that the input signal is the output squared. Great for triangular / squarish tones, including a pure 'shark-fin' wave when the FM depth is somewhere between 25 and 30.

Mono / Stereo

Like the OSC module, the FMO can also run in stereo mode. This is hardly noticeable unless the FMO is detuned and Width is turned up because, unlike OSC modules, the phase of an FMO is always reset to zero when a note is played.

Tune

FMO pitch offset (+/- 48 semitones).

Detune

If the FMO is in mono mode, Detune lowers or raises the pitch by +/- 50 cents. In stereo mode, it is a detune *spread* – it sharpens the left channel and flattens the right channel at the same time. Of course you can still fine tune the FMO via Shift+Tune.

Width

Stereo spread while the FMO is in stereo mode.

Vibrato

The amount of pitch modulation directly from LFO1 (0 – 100). The maximum depth here is only +/- 50 cents. If you need deeper vibrato, click on the assignable knob below 'Tune', select LFO1 from the list and set the amount to about 1.00.

Pan

Shifts the stereo position to the left or right. Works for mono or stereo (see above).

Volume

Output level.

FM

Generally FM depth / input level – see *TYPE* on the previous page for details.

FMO lower panel

Like the standard oscillators, the FMOs use the lower panel for extra parameters. Unlike the standard oscillators, all four FMOs share the same panel:



part of the FMO lower panel

Generator Mode (rectangular icon)

Click to select from a list of alternatives to the standard sine wave. The current mode appears to the right of the graphic – for the FMO1 in this screenshot it is *pure sine*, for FMO2 it is *quadric shift*.

Key Scale Pitch (unlabelled horizontal slider)

MIDI note to FMO pitch, -200 to 200 centred around the note E2. A bipolar 'KeyFol' for the FMO modules. Double-click to set the default 100 (perfect semitones).

KEY SCALE / GAIN

MIDI note to FMO gain scaling. The horizontal axis is the full 8 octaves of MIDI notes and the vertical axis is the volume of the FMO from 0 to 100%, independent of the FMO's regular Volume setting. This feature can be used to balance volumes across the keyboard, for instance, or to define 'keyboard splits'.

VELOCITY / GAIN

Velocity to FMO gain scaling. The horizontal axis is MIDI velocity from 0 (actually 1) to 127 and the vertical axis is the volume of the FMO from 0 to 100%, independent of the FMO's regular Volume setting. This feature can be used to create velocity cross-fades between oscillators or even define velocity-switching (see FMO1 in the above image).

Noise

Noise has traditionally been used for percussive sounds, wind effects, explosions etc..



Noise module panel

TYPE

A choice of four different flavours of noise:

White is a random signal with equal power across the spectrum.

Pink is darker – high frequencies are attenuated by 3dB / octave.

Digital is a square wave with random polarity, like a very lo-fi oscillator. It can be played in tune if LP Cutoff is modulated by KeyFol with the amount set to 64.00.

Crackles produces random impulses, like a Geiger counter or a worn-out vinyl record.

Mono / Stereo

Even the noise modules can be stereo. See *Width* below.

LP Cutoff, HP Cutoff

Lowpass and highpass filters. In both *White* and *Pink* modes, the LP is 6dB/octave, as is the HP. In *Digital* mode, the LP is actually pitch, while the HP adds more irregularities. In *Crackles* mode, the HP reduces the probability of impulses.

Pan

Shifts the stereo position towards the left or right channels.

Volume

Noise output level.

Width

Controls stereo spread if the stereo switch is on. See *Mono/Stereo* above.

VCF

VCF stands for Voltage Controlled Filter. Although there are no high voltages in Zebra2 pushing and pulling electrons around, but most of Zebra's VCF types are almost as 'alive' as their analogue forbears. Note: The VCF modules are less CPU-hungry than the XMF modules (see 2 pages down).



VCF module panel

Filter Types

<i>LP Xcite</i>	24dB lowpass, with a frequency-dependent exciter as Drive, adding high frequencies.
<i>LP Allround</i>	CPU-friendly 24dB lowpass, with a strong resonance and smooth coloration via Drive.
<i>LP MidDrive</i>	Boosts mid-range frequencies via Drive, good for leads that can cut through the mix.
<i>LP OldDrive</i>	Adds even-numbered harmonics, for a vintage sound bordering on 'cheesy'!
<i>LP Formant</i>	Vocal filter type combining a non-resonant 12dB/octave lowpass with a resonant formant stage. The Formant parameter replaces resonance, and the vowel parameter morphs through A–E–I–O–U . Great for 'singing' voices and vocoder-like pads. Note: The mod target of the righthand assignable knob is the <i>Vowel</i> parameter!
<i>LP Vintage</i>	CPU-cheap analogue-modeled transistor ladder with 24dB rolloff.
<i>LP 12dB</i>	A 12dB version of LP Allround
<i>LP 6dB</i>	A simple lowpass with a very shallow rolloff, non-resonant
<i>BP RezBand</i>	A resonant 12dB bandpass model
<i>BP QBand</i>	Another resonant bandpass, with a different character
<i>HP 24dB</i>	Resonant 24dB highpass
<i>HP 12dB</i>	12dB version of the above
<i>BR Notch</i>	24dB band reject

<i>EQ Peaking</i>	Peak / reject filter, like parametric ‘mid’ on a mixer. Res controls the slope of the peak. Gain has a range of -20dB (deep notch) to +24dB (strong peak). This type has little or no effect if Gain is zero.
<i>EQ LoShelf</i> <i>EQ HiShelf</i>	Two shelving models, to complete the trio of ‘parametric EQ’ filters. Like in EQ Peaking, Gain attenuates or boosts the frequency range (low or high), and the Res parameter controls the slope.
<i>AP Phaser4</i> <i>AP Phaser8</i>	The two phasing models use 4 or 8 stage all-pass (AP) filters to generate typical phasing effects. Cutoff controls the center frequency, and Res controls intensity. In the Phaser8 model, the Split parameter detunes the 8 stages.
<i>LP Vintage2</i>	CPU-intensive version of LP Vintage, capable of self-oscillation.
<i>SR Decimate</i>	Not really a filter, this is a sample-rate reduction processor. The Cutoff parameter controls rate, meaning it can be tuned harmonically (set KeyF to 100). Neither Res nor Drive are used.
<i>LP TN6SVF *</i>	TyrellN6 ’s state variable lowpass. An octave higher than other types!
<i>LP MS2035 *</i>	Early version of Diva ’s rev1 BITE lowpass
<i>LP S20SK *</i>	Early version of Diva’s rev2 BITE lowpass

* The last 3 were included by mistake in a previous version of Zebra, and reintroduced for compatibility reasons. Note: the CPU hit is significantly higher than the other types.

Controls

Cutoff

The *Cutoff* determines a filter’s edge-frequency. Like all frequency parameters in Zebra2, the scale is in semitones, as tuning cutoff in musical terms makes more sense than the very scientific ‘Hertz’. With KeyF (key follow) turned down, the cutoff values of most filter types correspond to MIDI note numbers minus 12 (one octave). For instance, with cutoff set to 81.00 a filter would resonate at 440Hz (middle A).

Resonance

Resonance is an internal feedback loop that emphasizes the cutoff frequency. In some filter types (e.g. EQ Peaking), this parameter is actually a Q-factor, the slope of a band centred around the cutoff frequency.

KeyF

The ‘key follow’ parameter adjusts how strongly the cutoff follows MIDI notes (the higher the note, the higher the cutoff). At 100%, it follows semitones precisely.

Drive / Gain

The Drive or Gain parameter of a filter usually adds some kind of distortion. In Zebra’s VCF this is more of a generic ‘flavour’ parameter – see the remarks in the above list.

XMF

The XMF (cross-modulation filter) module is an extremely flexible multimode filter featuring self-oscillation, input-dependent distortion and audio-rate FM via the extra input. The XMF is more CPU-intensive than any of the VCF models. For more details, see the flow diagrams towards the end of this document.



XMF module panel

There are 15 filter types / combinations, but you actually have **two of these** in stereo, with differential cutoff. So if you ever need a 3-pole allpass in parallel (or series) with a 2-pole bandreject / lowpass combination... no problem!

Distortion in the XMF is highly dependent on the level of the input signals – they affect the sound as much as Overload does. You should try e.g. oscillator volumes as low as 2%!

Filter Types

From top to bottom, the four switches in the window are: *Type1*, ***Routing***, *Type2*, ***Driver***.

Type1

LP4, LP3, LP2, LP1Lowpass modes, 4 slopes (24, 18, 12 and 6 dB per octave).

HP3, HP2, HP1Highpass models, three different slopes

BP4, BP2.....Bandpass, two different slopes.

BR2Bandreject, 2-pole only

AP3.....Allpass, 3-pole only

HP3LP, HP2LP.....Combination of 3-pole or 2-pole highpass + 2-pole lowpass

BR2LPCombination of 2-pole bandreject + 2-pole lowpass

AP3LP.....Combination of 3-pole allpass + 2-pole lowpass.

Routing (R)

Each XMF module has two stereo filters, which can be routed in four different ways:

singleStandard mode. Actually two filters with stereo-splittable cutoff values for spectacular panning effects – try modulating Offset with an LFO.

serial.....Type1 filter is fed into the Type2 filter.

parallel.....Type1 and Type2 filters are output separately.

diff'edThe difference signal (Type1 minus Type2). Note that if the two types are the same and there is zero offset, the result is total cancellation.

Type2

sameType2 adopts the Type1 setting. For all other options, see the Type1 list.

Driver (D)

Five options for the resonance / overload character. Note that output volumes can vary depending on the Resonance and Overload values (see below).

XMFStandard high-quality – plenty of bite.

analogueClassic ladder filter overdrive – warm / dark.

biasedDiode-like asymmetrical distortion, for more even-numbered harmonics.

ecoCPU-friendly version of analogue, lower quality Overload (see below).

foldedPositive peaks that would otherwise clip are folded back down.

Controls

Cutoff

Cutoff determines the filter's edge-frequency. Like all frequency parameters in Zebra2, the scale is in semitones – tuning cutoff in musical terms makes more sense than the more scientific 'Hertz'. Cutoff values correspond to standard MIDI note numbers minus 12 (one octave), so 81.00 means a middle A (440Hz) before any modulation.

Res (resonance)

Resonance is an internal feedback loop that emphasizes the cutoff frequencies. High resonance is very interesting in combination with Overload. Set Resonance to maximum, and the filter will self-oscillate (see *Click* below).

KeyF

KeyFollow, the depth of cutoff modulation from MIDI note / keyboard. At 100%, it follows semitones perfectly. Note that the breakpoint (the key that doesn't change) here is E2.

Offset

Splits the cutoff values of the two channels, in semitones (+/-48). Great for panning effects with the standard *single* routing, or for multiple resonances in *serial*, *parallel* or *diff'ed* mode (see the previous page). *Offset* has a assignable modulation knob.

FM

For audio-rate cutoff modulation ('Filter FM') from the XMF's second input. By default, the FM source is the same as the input signal, but using a different FM source can be highly rewarding: right-click on the [XMF] cell to change the sidechain input to another lane – and put something in that lane! *FM* also has a assignable modulation knob.

Over (overload)

Pushes the filter 'too far'! For interesting distortion effects and general oomph. Note that high overload can amplify the signal a lot – you might need to reduce the level elsewhere e.g. the volume control of the lane you are using. See also *Character* above.

Click

Injects a short impulse into the filter at the start of each note. Turn up for harder attacks or more instantaneous self-oscillation.

Comb

Comb ‘filters’ are based on ultra-short delay lines with feedback. Even if the input is a very short impulse, the feedback can turn it into a slowly decaying or even sustaining tone. The frequency response curve resembles a regular row of spikes, hence the name.



Comb module panel

You can create envelope-driven polyphonic flangers, realistic plucked and bowed strings, flutes, mallet and other percussion instruments... but remember to turn up *Feedb*!

Switches

MODE

Comb A simple stereo delay tuned to the played note. Note: In this mode, neither Tone nor Flavour have any effect.

Split Comb Any input is summed to mono and fed to the first of two delays, which then cross-feed each other. In this mode, Tone is the ratio between the delay times, while Flavour controls the amount of input signal fed directly into the second delay. The output is split: the left channel is delay 1 and the right channel is delay 2.

Split Dual The same as *Split Comb* except that input signal is not summed to mono.

Diff Comb The same as *Split Dual* except that the second ‘delay’ is actually an all-pass filter. This mode is especially good for strange, complex sounds. The Flavour parameter is the feedback of the allpass filter. As non-harmonic frequencies can dominate, you may have to tune this one very carefully.

Dissonant A 4x4 feedback delay network. Metallic. The Tone and Flavour parameters both affect the delay ratios (i.e. the pitches), but Distort is unused.

Cluster Experimental, included for compatibility reasons: Use at your own risk!

Blown This mode uses a bandpass filter in the feedback path to accentuate harmonics rather than the fundamental. Modulating the Flavour parameter is especially interesting. You can get very realistic flutes and trumpets etc., but it does require careful tuning.

PREFILL TYPE

The comb has an impulse generator so it can generate sound without requiring an input signal. The impulse can be one of three different waveforms:

Noise.....a short burst of white noise, different for each note

Saw.....a single cycle sawtooth (full / warm)

Square.....a single cycle square wave (hollow, nasal)

SOUND, OUTPUT

These tabs swap out the bottom row of knobs – see the next page.

Main controls



Comb panel, main controls

PreFill

The level of the internal impulse signal. See *Impulse* above.

Tune

Nominal pitch. The range is +/-24 semitones.

Detune

For *Split Comb* this is normal fine tuning. In other modes it detunes in both directions.

Vibrato

Amount of pitch modulation directly from LFO1 (0 – 100), with a range of +/- 50 cents.

Input

Input level. Negative values invert the signal to be processed, so you can use the Comb module as an audio signal inverter.

Damp

A 6dB lowpass filter in the feedback path simulates how a plucked string is naturally dampened by various physical constraints.

Feedbk

Bipolar feedback level control. Negative values lower the pitch by an octave, and the timbre is more hollow.

SOUND



Comb panel, SOUND sub-panel

Tone

The function of this parameter changes from mode to mode. Usually a ratio between delay times. For details, see [MODE](#) above.

Flavour

The function of this parameter changes from mode to mode. Usually a level within one or more feedback paths. For details, see [MODE](#) above.

Distort

Distortion adds harmonics into the feedback. Use with caution!

KeyScale

MIDI note to pitch, centered around the note E2. Effectively a bipolar 'KeyFol' for the comb. Leave at 100.00 for semitone steps (a double-click takes you straight to 100). For flanging and resonance effects, set KeyScale to 0.00 and take the Tune value down.

OUTPUT



Comb panel, OUTPUT sub-panel

Volume

Comb output level. Careful! If this reaches zero either through modulation or simply by turning down the Volume knob, the Dry signal suddenly shoots up to 100%. Whether this is a feature or a bug, it can make interesting rhythms – try modulating Volume from an LFO, and adjusting the Volume knob.

Pan

Panorama shifts the stereo position of the processed signal towards the left or right. Pan does not affect the position(s) of the Dry signal.

Dry

Unprocessed “throughput” from whatever is fed into the Comb.

Width

Stereo separation of the processed signal. Does not affect the Dry signal.

SB (Sideband)

The Sideband module is a stereo frequency shifter, the origins of which go back to the early days of radio. Related to ring modulation in which two signals are multiplied, resulting in two 'sidebands'. The Sideband module can also lend the signal a metallic character, as frequencies are shifted by a constant (e.g. 100Hz) instead of a factor (e.g. 2.00 times). While the 'beating' effect of mild oscillator detuning can become irritatingly fast when you play higher up the keyboard, frequency shifting keeps this effect constant.



SideBand module panel

Range

The SB module offers 3 bipolar frequency range options, which all start at 0Hz (center):

10Hz.....for relatively slow-moving cyclical effects e.g. stereo phasing.

200Hzfor low-frequency effects e.g. deep bells, rumbles... or even phone dial-tones

4kHzfor high-frequency or very wide range effects

Freq

Bipolar frequency shift. Positive values make the upper sideband louder.

Offset

Bipolar offset between left and right channels. Great for stereo rotary effects. Offset can be used for a special kind of phasing that continually rises in the left channel, while continually falling in the right channel. Check this out in headphones: Set the range to 10Hz, Freq to zero, Offset to 2.00, Mix to 50 – and feed it a medium dose of pink noise!

Mix

Bipolar cross-fade between the original signal and the frequency-shifted signal. Negative values invert the processed signal. For maximum phasing effects, set to +/-50.

Shape

The Shapers are input level dependent distortion units with a choice of 4 algorithms.



Shaper module panel

TYPE

Shape Classic waveshaper. The Depth parameter adds a DC bias before the shaper, making it positively asymmetrical (for even-numbered harmonics like ‘tube’ distortion). Note that the DC bias can considerably reduce signal level.

T-Drive Frequency-dependent waveshaper, like a transformer. Can boost ‘presence’.

Crush Bit-reduction via Depth knob. Neither Input nor HiOut are used in this mode.

Wedge A high-order waveshaper with foldback function (loud signals can become silent or even phase-inverted). The Depth knob boosts the input signal, controlling the distortion amount. Positioned after a resonant filter this type can emulate ‘acid basslines’.

Depth

Distortion threshold, effectively a distortion amount control. Like a guitar amplifier, every knob in this module affects the amount of distortion in some way or other!

Edge

The main tone control.

Input / Output

Attenuate / boost the input and output signals. Also affects tone...

HiOut

Attenuates / amplifies high frequencies – the final tone control in this module!

Distortion

The Distortion module creates traditional analogue-type saturation. If used in the FX Grid, it can mimic a complete guitar amplifier and speaker cabinet.

input amp → pre tilt filter → distortion → post tilt filter → post filter → output amp



Distortion module panel

TYPE

Tube Class A Simulates a complete tube preamplifier. Class-A is the 'traditional' type of tube distortion, creating both odd and even harmonics by using a single tube and applying DC bias. Due to the asymmetry of the operational curve, Class A distortion sounds relatively warm.

Tube Class AB Simulates a preamplifier with two tubes in a ‘push-pull’ arrangement, which leads to symmetrical distortion with no even-harmonic partials.

- Tube 2 Stages**.....Mimics a tube amplifier with two class-A stages in series. Like class A, this also creates odd and even harmonics, but the results are richer and more dynamic. This mode applies additional internal filtering and feedback for more sonic complexity. At high gain settings you should hear more pronounced treble roll-off and more bass lift.
- Hard Clip**.....This mode simply chops off the top and bottom of the waveform.
- Rectify**.....Full-wave rectification. The negative half-wave becomes positive and the resulting waveform is fed through a DC-blocking filter. Interesting note: A pure triangle wave will be simply doubled in frequency, without altering the waveform.
- Foldback**.....Also known as 'fold-over distortion'. *Foldback* is similar to soft clipping, except that increasing the gain does not slam the signal against the ceiling (it reduces the gain instead). Listen out for strange inter-modulation artifacts!

Input, Output

Sets the gain (in decibels) at the input

Output

Sets the final output gain. Note that this stage includes soft clipping, which can create even more distortion when turned up 'too high'

Pre Tilt

A combination of low and high-shelving EQ is applied to the input signal, and Pre-Tilt makes the distortion frequency-dependent (at zero, the response remains flat). Negative Pre-Tilt strengthens the bass and dampens the treble, positive values strengthen the treble and dampen the bass.

Center Freq

Combined low and high shelf frequency control.

Post Tilt

Use this to balance the tone (in a similar manner to Pre-Tilt) *after* the distortion.

Low and High

In *Dual-Band Shelf* mode (see Post Filter below), these knobs control the gains of the shelving filters. In *Guitar Cab 4x12* mode they determine the amount of cabinet resonance i.e. bass and speaker 'edge'.

POST FILTER

Dual-Band Shelf: This is a simple corrective EQ – a low shelf fixed at 100Hz and a high shelf fixed at 10kHz. See *Low and High* above.


Guitar Cab 4x12: This mode mimics the frequency response of a very popular vintage speaker cabinet, producing its typical mid-range focused sound (including peaks and dips caused by resonance within the cabinet as well as the effects of close miking).

Ring

Ring modulation is a variant of amplitude modulation (AM): Two input signals are balanced so that they disappear completely, leaving only the sum and difference frequencies. These frequencies are seldom harmonically related, so ring modulation is often used for bell-type sounds. For the purest results, use sine waves – FMOs and/or *SpectroBlend* OSCs.

The ring modulators in Zebra2 don't require a panel, but they do need two input signals. The image to the right is the result of right-clicking on the 'Ring1' cell. **SideChain 2** is selected so that FMO1 is being ring modulated with OSC 1.

The circuit originally used to implement this technique in analogue devices had the shape of a ring, hence the name. With today's computers, ring modulation is very easy to achieve: the two signals are simply multiplied.



Mix

This modules can mix two signals, it can be used for cross-fading ('Mix' is a modulation target) or for reducing stereo width: Select 'Pan Mono' and set Mix to 100 – you will only hear the sidechain signal now, fully mono.



Mix module panel

Mixers can often be avoided. In the lefthand image here, Mix1 was added so that the unfiltered signal could be sent down lane 2 to be treated separately (FX). However, the mixer isn't actually necessary for this patch, as the arrangement on the right does the same job.



PAN MODE

Bal L-R, Pan L-R, Bal R-L, Pan R-L and Pan Mono.

With the Pan knob set to the center, the two *Balance* modes have 0dB of gain for both channels – only one channel is attenuated as the control is moved away from the center position. The *Pan L-R* and *Pan R-L* modes, however, mix one channel onto the other while adhering to the *Pan Law* (google those two words!)

Pan, Mix

The stereo position and relative levels of the two inputs.

Fold

A ‘wavefolder’ is a special kind of waveshaper which maps the input signal onto a sine, folding it back on itself multiple times. Like hardware wavefolders, Zebra2’s *Fold* sounds best when applied to signals with very little high frequency content – try a pure FMO first.



Fold module panel with 6 Ripples, 22% Folds, 30% Bias and maximum Slope

Ripples

The total number of cycles, from 1 to 7.

Live View

This button activates realtime animation of any *Folds* and *Bias* modulation. If you need to save CPU, leave it disabled.

Folds

The percentage of Ripples used. Note: As it is effectively an input level control, setting *Folds* to zero without any modulation will result in silence.

Bias

This parameter shifts the used section of the curve to the left or right. Bias modulation is applied in opposite directions per stereo channel, resulting in a unique stereo effect.

Ratio

The relative level of the ripples, effectively an output boost control.

Slope

Tilts the curve downwards or upwards.

Soft Clip

The smoothness of the two ‘knees’ to the left and right of the ripples.

Note: *Fold* is highly sensitive to variations in signal levels and phase between the various sample rates. If your preset sounds too different after switching to a higher sample rate, try adjusting the *Folds* parameter, then save as “name-of-preset (96k)” or similar.

Modulators

Modulation is what we use to turn static tones into interesting instruments or soundscapes. Zebra2 lets you modulate practically any 'target' parameter in the synth. As well as LFOs and envelopes, the list of modulators include standard MIDI messages for external control: pitchbend, mod-wheel (CC#01), polyphonic or channel aftertouch, velocity and Gate.

Notes: Practically all the controls can be automated. Using the X/Y performance pads is the best way to control a lot of parameters at once, and they can also be automated.

List of Modulation Sources

ModWhl	modulation wheel (CC#01)
PitchW	pitch wheel / pitch bender
CtrlA	MIDI control A, default = Breath (CC#02)
CtrlB	MIDI control B, default = Expression (CC#11)
LfoG(1,2)	global LFOs
Gate	note on/off
KeyFol(2)	key follow (center = E2) + glide. (2) includes glide offset
Velocity	MIDI note velocity
ATouch	channel or key (polyphonic) aftertouch, smoothened.
ArpMod(1,2)	arpeggiator modulation
Env(1-4)	standard envelopes
MSEG(1-4)	Multi-Stage Envelope Generators
Lfo(1-4)	voice LFOs
MMap(1,2)	modulation mappers
MMix(1-4)	modulation mixers

For a complete list of all modulation **targets**, go [here](#).

Modulation Matrix

All generator panels include assignable knobs (unused ones appear with an ellipsis ... as label) for setting up local modulation. The mod matrix is where you can set up any kind of modulation – the image below shows just three of the twelve modulation slots...

SRC

The lefthand knob selects the primary modulator and sets its (bipolar) amount.

VIA

The righthand knob sets the amount that a secondary modulator affects how much of the primary modulator reaches its target. Odd behaviour: When the VIA source is at minimum, negative amounts of VIA scale the modulation depth from 100% to 200%.

TARGET

The parameter to be modulated. Because of the recently implemented drag & drop function (see below), opening the list of modulation targets now requires a right-click.

Two examples: In slot 10, Env2 decay is negatively modulated by Aftertouch: The harder you press, the shorter the decay.

In slot 11, Env2 modulates oscillator detuning, at 100%. However, this amount is partially *scaled* by the mod wheel – the amount of Env2 reaching its target will be less than maximum until the mod wheel is at maximum. If 'VIA' is set to +100% instead, none of the Env2 signal will reach the oscillator unless the wheel is pushed.



Drag & Drop

As a quick alternative to selecting a target from the menu, you can use Drag & Drop. Left-click on a Target selector, drag the crosshair onto a control in the Synthesis page then release the mouse button.

Of course you don't have drag & drop access to any of the controls in the lower pane (Global, Osc 1, Osc 2 etc.), but these are available in the target's context menu.

Tricky Intervals

Setting precise pitch intervals in the modulation matrix requires a bit of arithmetic, as the 96 semitone range (+/- 4 octaves) is mapped onto 100 steps. For instance:

12 semitones (octave)	$100 / 96 \times 12 =$	12.50	absolutely precise
7 semitones (a fifth)	$100 / 96 \times 7 =$	07.29	also try 07.30 and 07.31
1 semitone	$100 / 96 =$	1.04	more precisely 1.04167

Note: If the modulation source is bipolar e.g. an LFO, you should halve the modulation amount, as the 96 semitone range is mapped onto 200 steps instead (-100 to +100).

ENV

When you load *init*, envelope 1 is already visible in the modulators pane because in this preset it is designated as the audio envelope for all 4 lanes of the main grid.



an ENV module in v-slope mode

Although it looks like a regular ADSR with just a few extras, the ENV module has several tricks up its sleeve: It is syncable, loopable, and offers 2-stage attack or release...

Switches

TIME BASE

8sX.....up to 8 seconds, knob scale is exponential (mid-position is 1 second)
 16sX.....up to 16 seconds, knob scale is exponential (mid-position is 2 seconds)
 10s.....up to 10 seconds, knob scale is linear, so 20.00 means 2 seconds etc.
 1/4, 1/1, 4/1times are relative to song tempo (beat, bar, 4 bars), knob scale is linear


MODE

Specifies the curvature of all time-based envelope stages. There are 3 options:

quadric.....exponential curves. Attack is convex, Decay and Release are concave

linear.....straight lines. Linear envelopes can sound unnatural

v-slope.....exponential curvature via slider: the far left position is very concave, -50 is close to quadric, the center is linear, the far right is very convex



*Main ADSR envelope stages, here with Init and Delay **Pre-Attack** (see the next page)*

Controls

Pre-Attack

Although it resembles assignable modulation, the top lefthand knob actually controls one of two parameters at the beginning of the envelope:

Init: The Attack stage starts at a level other than zero (see left-hand image above)

Delay: The Attack stage is delayed (see right-hand image above)

Attack

The time it takes for the envelope to rise from zero (or the *Init* value) to maximum

Decay

The time it takes to drop from maximum to the Sustain level

Sustain

The level after Decay. Normally remains at that position until the note is released

The extra envelope stages below can be tricky. If you prefer regular ADSRs, simply ignore the following options...

F/R (Fall / Rise time)

Negative values: either fall to zero, or fall/rise to the Sust2 level (see Post-Sustain)

Positive values: either rise to maximum, or fall/rise to the Sust2 level

Post-Sustain

This knob is NOT for assignable modulation, but for the following extra options:

Sust2.....a second Sustain level, after F/R


LoopA.....loop back to Attack

LoopD.....loop back to Decay


LoopS.....loop back to Sustain

Rel(nn)extra release stage (the 'nn' numbers are percentages of maximum level)


Note: The diagrams below are simplifications. For example, Release (or Rel25/50/75/100) can start at any point within the envelope, as it is initiated by a MIDI Note Off message.




Normal F/R behaviour, no Sust2 stage




*F/R behaviour when there is a Sust2 stage
(two possible Sust2 values shown here)*




LoopA: Time to return from end of F/R (100 or zero) to zero (start of Attack).



LoopD: Time to return from end of F/R (100 or zero) to 100 (start of Decay)



LoopS: Time to return from end of F/R (100 or zero) to Sustain level.



Rel25/50/75/100: Time to rise or fall from Sustain to 25/50/75/100%, followed by the normal Release stage.

Release

The time it takes to drop to zero after a note is released. See also *Rel(nn)* above.

Velocity

For dynamic envelopes – keyboard velocity scales the envelope's output level.

VELOCITY SCALE and KEY SCALE

To see these controls, click on the **[+]** icon in the top righthand corner of the panel.




ENV module, with scaling sub-panel open

All these knobs correspond to the parameters in the upper sub-panel. For instance, positive Velocity Scale for Decay will lengthen the decay times as you play harder, and negative Key Scale for Release will shorten the release times of higher notes, etc..

MSEG

The Multi Stage Envelope Generator is a complex modulation source offering total shape control as well as continuous rate control. Click on the MSEG 1 button in the lower bar...



Many different uses for MSEGs can be found in the factory presets. A few examples:

Rhythms:	6 Lupins / Twangle
Pitches:	6 Lupins / Seven of Eight (MSEG 3)
Multiple attacks:	8 Perkors / Drums of Mordor+ (MSEG 1 and 2)
Combinations:	2 Leaders / I am Zebra (All 4 MSEGs)
Snappy envelopes:	6 Lupins / How Money More Times
Twisted regularity:	7 Noises / Combotor (MSEG 2, MATRIX slot 02)

Controls

Preset (unlabeled)

Like the oscillators, MSEGs can be loaded and saved. Click on the long button to load from the mini-browser, or right-click to select from a menu or save to the current folder.

The MSEG browser's context menu includes 'refresh' and 'open in...' functions – use these whenever you want to transfer MSEG templates to other computers.

Time Unit

Selects the unit that will correspond to integer steps in the editor's time-line. Note that the timing can always be shifted by setting non-zero Attack, Loop or Release values.

Sixteenth / Quarters / Notes: These are note lengths, synchronized to song tempo.

Seconds: Units are 4 seconds long. For seconds, set Attack / Loop / Release to 2.00.

Trigger

polystandard polyphonic

singleonly retriggers after all notes are released (like organ "percussion" register)

monostandard monophonic

Attack

Slows down / speeds up everything before the loop. -1.00 is half speed, 1.00 is double speed, 2.00 is quadruple speed etc..

Loop

Loop speed: -1.00 is half speed, 1.00 is double speed, 2.00 is quadruple speed etc..

Release

Slows down / speeds up everything after the loop. -1.00 is half speed, 1.00 is double speed, 2.00 is quadruple speed etc..

Velocity

For dynamic envelopes – velocity controls the MSEG output level, as a percentage.

Editor functions

Expand

For a larger EDITOR, click on the vertical label to the left of the data area. To exit again, click on the same button (conveniently renamed “CLOSE”).

While an MSEG is expanded, the lower pane becomes an editable list of all its uses, either as assignable knobs in the panels, or in the modulation matrix. Modulation depths can be adjusted here, either by moving the slider left-right or the VALUE vertically.

Source assignments can even be added by clicking on the *Add* button. To remove an assignment, click on the [x] button to the right.

Edit Mode Switches



Above the MSEG1 selector button are three small icons. From left to right, these are:

Single.....moves individual handles, the other handles remain fixed

Shiftmoves individual handles, all following handles also move

Drawmoves multiple handles vertically – click on a handle and ‘draw’

Note that handles will jump to the nearest *unit snap* and *value snap* positions if these are defined (see *Context Menu* on the next page).

Create New Handle (max. = 33)

Maccmd + click on the background

Winalt + click on the background

Curvature

Click on a line and drag it in any direction to adjust the curvature. S-curves are also possible: Hands-on experience is better than a detailed explanation here. To straighten a curve, left-click on it and release immediately.

Zoom & Scroll

To zoom in or out, click on the background and drag up or down. For ‘optimum’ zoom, double-click in the background. To scroll to invisible sections of the envelope, click and drag left / right.

Context Menu (right-click in the **background**)

Copy / Pasteclipboard functions
Half Sizeshortens the envelope
Double Sizelengthens the envelope
Upside Downinverts the envelope
Unit Snaphorizontally restricts new input to 3, 4, 6 or 8 steps per unit
Value Snapvertically restricts new input to 12, 24, 36, 48 or 15 levels
Quantise to Snapquantizes all points to the nearest step (see *unit snap*)
Unit Spacingdistributes all points to successive units
Even Spacingevenly distributes all points
Pointer offto save CPU, hide the position indicator
Pointer coarsedefault resolution of the position indicator
Pointer finehigher resolution of the position indicator

Context Menu (right-click on a **point**)

Remove Point (min. = 2), *Loop Start* and *Loop End* are self-explanatory. To make a loop of zero length, delete the point currently set as 'loop end'. MSEGs continue looping after the note has been released if the loop end is set to the very last point.

LFO

Alongside envelopes, low frequency oscillators represent THE classic modulators – for vibrato or any cyclic movement e.g. a slowly drifting tonal change:



This is called a 'voice' (or polyphonic) LFO because, unlike the LFOG, it is instantiated per voice – every note you play gets its own LFO. The main advantage over the LFOG is that different notes in a chord can have different amplitudes, phases and rates.


In all OSC, FM and Comb modules, 'Vibrato' is permanently connected to LFO 1. To set up traditional vibrato control via mod-wheel, click on the knob to the left of 'Amp', select 'ModWhl' and turn the knob up... and turn up the 'Vibrato' levels!

WAVEFORM

sinepure sine wave
trianglepure triangle wave
saw uprising saw ('ramp')
saw downfalling saw
sqr lo-hisquare wave, restarted at the lower level
sqr hi-losquare wave, restarted at the higher level
rand holdrandom steps
rand gliderandom curves
userup to 32 steps, user-drawn...

User mode options

The MODE buttons on the right select either discrete levels (steps) or connecting lines:



The STEPS selector specifies the number of points, from 2 to 32.

Note that SYNC (see below) sets the length of **each step**, so a complete cycle in the upper example would be $16 * 1/16 = 1$ bar in 4/4 time.

A right-click anywhere in the LFO's edit window opens the same context menu as in the [modulation mapper](#), with the same set of useful [drawing tools](#). Try them!

SYNC

0.1s, 1s, 10s.....absolute time in seconds, three ranges

1/64 – 8/1.....synced to song tempo (includes dotted and triplets, maximum 8 bars)

RESTART

free: the LFO starts at a random position within its wave every time a note is played

gate: the LFO always starts at the same position in its wave (see Phase below)

SLEW

Smoothness: *off* can produce clicks, while *fast* and *slow* smooth out sharp transitions.

Rate

LFO rate. This bipolar control scales the value set by the SYNC parameter.

Amp

Amplitude i.e. output level of the LFO. For typical “vibrato via modulation wheel”, click on the assignable knob and select *ModWhl* as source. Note that the assignable control *scales* the existing Amp value, it does not add to it.

Phase

Sets the phase (i.e. the position within its cycle) at which the LFO will be restarted every time a note is played. This parameter is meaningless if Restart is set to *free*.

Delay

Fade-in time. Typically used for so-called 'delayed vibrato'.

LFOG

The "LFO Global" module is simpler than the normal LFO: The assignable knobs and the Delay are missing, and the LFOG doesn't restart per voice – it is practically 'monophonic'.



LFOG module, sine wave, synced to 'beats' and retriggered every 3 bars

WAVEFORM

The LFOG offers the same waveform options as the LFO (see the list above).

SYNC

Basic rate (see Rate knob below).

0.1s, 1s, 10s.....absolute time in seconds, three ranges

1/64 – 8/1synced to song tempo (includes dotted and triplets, maximum 8 bars)

RESTART

Automatic restart after the specified number of bars (off i.e. no restart, or 1 to 32).

SLEW

off can produce clicks, while *fast* and *slow* smooth out any sharp transitions.

Rate

LFOG speed. This bipolar control *scales* the basic rate set by the SYNC switch.

Amp


Output level.

Phase


Sets the phase i.e. the position within its cycle at which the LFOG restarts. Ignored if RESTART (see above) is set to *off*.

MMap


The 4 **Modulation Mappers** are general purpose tables which can hold up to 128 user-defined values. Maps have a wide variety of uses, e.g. meticulously adjusting the tone of each note on across keyboard, as in this example (used in *HS Ligetimat*).



...or for 'round-robin' effects. Old polysynths had a limited number of voice circuits, and the tuning of e.g. pitch and cutoff was also fixed (via trimmers) for each voice. The example here simulates six of those trimmers (used in *HS Poppington*).



...or for remapping a modulation source. In this example (used in *HS Seed*), aftertouch has zero effect until the keys are pressed hard enough to reach the point where the curve starts to rise.



MODE

Specifies how the map is controlled. Note that the two *Map* modes won't do anything if you haven't defined a Modulator.

Keythe 128 MIDI notes (although nobody owns a keyboard that long)

Map Smooththe 128 modulator values, interpolated for smooth transitions

Map Quantizethe 128 modulator values, not smoothed

Incrementplayed notes step through the map

MODULATOR

This selector specifies a modulation source (LFO, envelope, whatever) to be mapped in either of the two *Map* modes. In *Key* or *Increment* mode, this setting is ignored.

Expand

Click on the 'window' icon to expand the map. In the first example above, precision isn't a problem as points can be selected by playing MIDI notes and the bars are 'magnetic'.

While a map is expanded, the lower pane becomes a list of all its uses. Modulation depths can be adjusted here, and source assignments can even be added by clicking on the *Add* button (please note that the current version doesn't allow assignments to be edited afterwards). To remove an assignment, click on its [x] button.

Selection / Drawing Tools

To edit a map, draw in the windows by clicking and dragging. To highlight a selection, hold down the **SHIFT** key while dragging. The various functions are restricted to the selection, if one exists. To deselect everything, either click in the background (i.e. away from the selection) or right-click and choose 'deselect' from the *selection* sub-menu...

Right-clicking on the modulation mapper's edit window opens a long list of editing tools. **Shift** is used for selection, and **alt** (Win) or **cmd** (Mac) is used for applying the selected *draw* option. Note: All these options also apply to LFO and LFOG in user mode!

Copy / Paste Clipboard functions for the map data. You can use these to transfer maps between presets.

Shapes Draw *Ramp*, *Triangle*, *Sine*, *Cosine*, *Root*, *Quadric* or *Spectralize*. The latter interprets the map as amplitudes of harmonics in the [harmonic series](#), then replaces the map with the calculated waveform (see [Spectralize](#) in the Tips & Tricks). If you use fewer than 128 values (see 2-128 below) the shape will be repeated to fill all positions.

Cmd-Draw Modify the shape by dragging in the editor while

Alt-Draw holding **cmd** (Mac) or **alt** (Win). The options are *erase* (set zero), *scale* (multiply), *shift* (2D move) or *warp* (2D bend).

Selection Applies functions to the selection: *invert*, *shift left*, *shift right*, *every 2nd/3rd/4th*. If nothing is selected, only the 'every' options will appear.

Reverse Flips the current selection horizontally

Invert Flips the current selection vertically

Randomize Adds random offsets to the selection

Soften Interpolates between values

Normalize Expands vertically to minimum / maximum

Make Unipolar shifts all values to positive, rescaling if necessary

Straighten Draws a straight line for the selection / window

Reset Sets all values in the map to zero

Quantize (n) Adjusts values to an equally-spaced grid. Tip: Select '12' here and use the map for pitch modulation (set the modulation depth in the osc to 12).

2-128 Map size i.e. number of values shown/used

Copy
Shapes ▶
Cmd-Draw ▶
Selection ▶
Reverse
Invert
Randomize
Soften
Normalize
Make Unipolar
Straighten
Reset
Quantise 4
Quantise 6
Quantise 8
Quantise 12
Quantise 16
Quantise 24
2
3
4
5
6
7
8
9
10
11
12
16
24
32
48
64
96
128
Lock

MMix

Zebra's **Modulation Mixer** processes up to 3 modulation sources in one of three ways...



The 3 MMix modes

MODE

sum modulationsAll 3 modulation sources plus the value of CON (constant) are added together – which saves work and Matrix slots if (for instance) you want to modulate several parameters at the same time from the same bunch of modulators!

scale sum by const.....The same as *sum* except that the result is multiplied by CON.

fade 1/2 by 3xC.....The constant determines how much of the Mod3 signal cross-fades between Mod1 and Mod2.

MOD1, MOD2, MOD3

Selectors for the 3 modulators.

CON

The constant is added to the output in *sum modulations* mode, it scales the output in *scale sum by constant* mode, or scales the amount of Mod3 in *fade 1/2 by 3xC* mode. Note that the CON value can be modulated, as it is a target in the modulation matrix.

Outputs and Effects

The FX Grid

Whenever you select Global in the lower bar, you will see the FX Grid in the middle of the lower pane. The principle is the same as the main grid, but with effect modules. For how to route signals from the main grid into the FX grid, see the section about the [Lane Mixer](#).

To add a new module, click on an empty cell. Double-click a module to switch it on/off. Right-click to select input(s) or remove the module.

Seven of the FX module types are the same as ‘processing’ generators available in the main grid: *Shape*, *Mix*, *Ring*, *VCF*, *SB*, *XMF* and *Dist*. The other six types – *ModFX*, *Delay*, *Rev*, *Comp*, *EQ* and *NuRev* – are described below.



FX Grid with example routing

Output controls

Send1 and Send2

These two knobs feed the *unprocessed input* of the MAIN lane into BUS 1 and BUS 2. In the image above, Send2 is feeding the SB3 module, and pushing the mod wheel turns the amount down to zero. See the [flow diagram](#) on page 112.

FX BYPASS

Click on this button (it turns dark orange) to temporarily deactivate all effects in the grid. The BYPASS status is truly global – you won’t hear any effects in any of your presets on any day of the week until you deactivate this!

MAIN, BUS 1 and BUS 2

Output levels for the left, center and righthand lanes of the FX grid. Note that these appear as *Master*, *Return1* and *Return2* in the data display and modulation matrix: Ignore!

OUTPUT

The final volume, the sum of MAIN, BUS1 and BUS2. OUTPUT is one of those few parameters in Zebra2 that cannot be modulated. Normally set to 12 o’clock (100%), a preset’s volume can be boosted up to 200% if necessary.

Note: This mirrors the OUTPUT knob in the [upper bar](#) – watch them move in tandem.

A note about modulating effect parameters

Zebra lets you use *any* source in the Matrix to modulate global parameters such as reverb size or delay feedback. However, many of the available modulators are instantiated per-voice (e.g. envelopes and LFOs). To avoid conflicting values, the effects only use the modulation provided by the most recently played voice. Depending on the modulation source, target and depth, this can result in audible glitches. We recommend using global sources such as the wheels, LfoG or MSEGs (in *single* or *mono* mode) wherever possible.

Modulation FX

Analogue purists may shudder at the mention of built-in **chorus** (which suggests a lack of ‘beef’ in other departments), but we believe no synthesizer should be without one:



ModFX panel, Chorus mode, equalizer On

MODE

Choruschorus / flanger using short delay lines

Phorus.....chorus / flanger using allpass filters

Phaser.....classic phaser unit

Feedback

Bipolar feedback control for ‘flanger’ type resonances.

Center

Nominal delay time / allpass cutoff.

Depth

Amount of *Center* modulation from the integrated LFO. See *Speed* below.

Stereo

LFO phase offset between the two stereo channels.

Note that 50% often delivers the widest effect.

Mix

Balance between the dry and wet signals.

Speed

The rate of the ModFX module's own LFO (0.1Hz to 1Hz).

Quad

The volume of an **additional** chorus effect, with independent LFO.

Q-Phase

Modulation LFO phase offset (see *Stereo* above) for the Quad effect.

EQUALIZER

A pair of low and high filters between the dry and chorused signal. These can be used to preserve the stereo position of bass frequencies while softening the chorus.

ON/OFF (unlabelled)

Switches ModFX equalization on or off

LO FREQ / LO BOOST

Low crossover frequency and gain for the dry signal.

HI FREQ / HI BOOST

High crossover frequency and gain for the dry signal.

Delay

The delay in Zebra2 is, as you should already have begun to suspect, very flexible. It has four delay lines, each with time scaling and pan controls. Two flavours of feedback with inserted low and highpass filters can run at the same time, feeding each other...



Delay module in stereo 2 mode (ping-pong regeneration via x-back)

MODE

stereo 2stereo delay, uses delay 1 and 2 only

multitap 4all four delays in parallel

dubby 2+2like two instances of stereo 2 in series

serial 2ping-pong delay, uses delay 1 and 2 only

For more details, see the flow diagrams towards the end of this document.

Feedback & X-back

Normal regeneration and cross-regeneration amounts. In multitap 4 mode, the X-back routing is 1 - 2 - 3 - 4 - 1 etc..

Lowpass, Hipass

Simple filters in the feedback paths affect the tonal quality of successive repeats.

Mix

Cross-fades between the dry and wet signal

Sync, Ratio & Pan

The button above each Ratio and Pan knob sets either a synchronized value (1/64th to 1/1 triplet) or absolute time (1 second). The Ratio knob scales this from 0% (4 samples long) to 200%. Pan is of course the stereo position of each delay line.

Tip: Try using a tiny amount of random LFOG to modulate one or two of the Ratios

Reverb

Zebra's original **Rev1** reverb unit. See also [NuRev](#).



Reverb panel, 'Reverb' mode

The upper row is the usual set of reverb parameters, and the lower row has a similar set of controls for the DIFFUSOR (diffusion adds more reflections, increasing reverb density).

Mode

Reverb is Zebra's standard model while *Metalverb* sounds more artificial and wider.

PreDelay

A delay before the reverb starts. Useful for retaining the presence of the dry signal while using lots of reverb. Or for slap-back effects with short Decay and small Size.

Range, D-Range

Reverb / Diffusion length i.e. delay times, from 'very short' to 'rather long'! Together, the *Range* and *Feedback* parameters shape the impression of room size.

Feedb, D-Feedb

How much of the reverb signal is fed back into the reverb input. If *Range* and *Feedback* are set to maximum and *Damp* is at zero, the reverb will carry on almost indefinitely.

Damp

A simple low pass filter in the feedback loop causes higher frequencies to fade faster than low frequencies, imitating the 'warming' effect of carpets, curtains etc. in a room, or the audience in a concert hall.

D-Mix

The amount of diffusion.

Speed, D-Speed

The rates of the LFOs modulating Range and Feedback / D-Range and D-Feedb.

Mod, D-Mod

The levels of the LFOs modulating Range and Feedback / D-Range and D-Feedb.

Dry, Wet

Separate controls for unprocessed and processed signal levels – modulating individual levels is more flexible than cross-fading dry/wet.

Compressor

Zebra's compressor module. If you are familiar with modular synthesizers, you can think of this as a stereo VCA being negatively controlled by an envelope follower.



The compressor in smooth mode

TYPE

ecooriginal lo-fi version, with very low CPU-hit.

smoothsmooth compression, the best choice for most sounds.

strongvery powerful compression, best for bold percussive sounds.

Threshold

Threshold sets the level above which compression will be applied, and below which compression will be released – so lower values will result in more compression than higher values.

Comp

Sets the amount of compression. Think of this as a dry/wet crossfade.

GR

Gain reduction indicator.

Attack

The time it takes to reach maximum compression after the threshold has been crossed. Attack can affect brightness: very fast values cause the compressor to reduce the gain immediately, which can dull the attack of the original sound. Note: When set to zero, the Attack is only one sample in length.

Release

Recovery time i.e. the time the compressor takes to return to unity gain after the input signal has fallen below the threshold. Very short Release can distort low-frequency input, overly long Release can 'clamp' the sound down and not release enough before the next 'attack' arrives. When set to zero, Release is only one sample in length.

Input


Adjusts the input level before the signal is compressed.

Output

Adjusts the output level to compensate for gain differences caused by the compression.

EQ

This module is a 4-band parametric equalizer. Drag the handles to set frequency and gain. Right-click on a handle and drag vertically to adjust the Q (width/slope) of the band. Right-click in the background for basic editing functions: copy, paste, clear (flatten).



Equalizer module, bass+treble boost, dip around 1 kHz

Alongside compression, equalization is the audio engineer's important "Swiss-army knife" used to ensure that tracks work well together in the context of the song.

In Zebra2, equalizers are very useful for tweaking the final tonal character of a preset – make it generally brighter or duller, boost or cut certain frequencies...

Freq LowShelf
Q LowShelf
Gain LowShelf

Freq Mid1

Q Mid1
Gain Mid1
Freq Mid2
Q Mid2
Gain Mid2
Freq HiShelf
Q HiShelf
Gain HiShelf

All 12 parameters (frequency, gain, slope) of the EQ are available in the Matrix as modulation targets. The highlighted entry in the menu here is actually the horizontal position of point 2:

Point 1 = *LowShelf*

Point 2 = *Mid1*

Point 3 = *Mid2*

Point 4 = *HiShelf*

Example: To use the EQ shown on the previous page as a swept band reject filter (sounds a bit like phasing), you need to modulate point 3 to the left and right. The modulation target is *Freq Mid2*.

NuRev

A smooth plate reverb with pre-delay. See also the original [Reverb](#).



The NuRev module

PreDelay

A delay before the reverb starts. Useful for retaining the presence of the dry signal while using lots of reverb. Or for slap-back effects with short Decay and small Size.

Damp

A low pass filter in the feedback loop causes higher frequencies to fade faster than low frequencies, imitating the 'warming' effect of carpets, curtains etc. in a room,.

Decay

Reflectivity of the room. Effectively how long it takes for the reverb tail to fade to silence.

Size

Room dimensions, from "sardine can" to infinity and beyond. Balance this with Decay...

Tone

Strong 'tilt' equalizer. Bipolar. Use in combination with Damp to "colourize" the reverb.

Width

Stereo spread of the reverb signal.


Dry/Wet

Balance between the dry and processed signals. At maximum, the dry component is faded out completely, allowing NuRev to be used for colourful 'guitar body' type resonances: Try setting *PreDelay* to minimum, then fine-tune the *Size* around 5.00.

Performance

Arpeggiator / Sequencer Programming

The arpeggiator is activated in the GLOBAL panel – see step 5 below and the [voice mode](#). If you would like to experiment with an existing arpeggio, load *How Money More Times* (for example) from the ‘Lupins’ folder and play with all settings...



Arpeggiator settings used in the preset ‘How Money More Times’

...or you can follow these steps

Hands-on tutorial

1. Right-click on the data display and select *init*.
2. Click below the OSC1 cell and add VCF1. The Synthesis window automatically opens.
3. Set VCF1 Cutoff to minimum, click on an assignable knob in the VCF and select Env1
4. Set the amount of ‘Env1’ cutoff modulation in the VCF to about 110, the Sustain of Envelope 1 to minimum, and Release to 50.
5. Click on the GLOBAL tab in the lower bar and select the *arpeggiator* voice MODE.
6. Play a low note...
7. In OSC1 change the STACK mode to ‘dual’, and Detune it to taste.
8. Play a low note and adjust VCF1 Resonance to about 10 (or higher if you prefer).
9. We should now have a simple bass arpeggio. Click on the ARP/SEQ tab in the lower bar to open the arpeggiator...
10. Change Steps to 4 and SYNC to 1/8. Change Transp (transposition) of the 3rd step to 1 and the 4th step to 7. Hold a note or two...
11. Change the leftmost triangle to a different icon. Why is it an 8-note sequence now? Experiment – listen to what happens if you change one or two of the other triangles.
12. Play a chord. Change the first four ‘Voices’ to 6 (roll your mouse wheel to do this)
13. Play a high chord. If it distorts, turn down the volume in Lane 1.
14. Click on the remaining assignable knob in the VCF, select ‘ArpMod’ and set the amount to +20. Click on the +A button next to the SEQ button and move the first four ‘A’ sliders to different values. Play and listen.

Now try adjusting all Lengths, Gates etc.. Then add ‘1/8 dot’ delay, of course!

Selectors

That block of controls on the left...



SEQ, +A, +AB

At the top of the panel are 3 mutually exclusive 'radio buttons': Show the sequence only, also include step modulator A, or include both **arpeggiator modulators**.

These bipolar values appear as *ArpMod* and *ArpMod2* in the matrix, and can be used for modulating anything you like (e.g. filter cutoff) in step with the arpeggiator.

Sync

1/64 – 1/1 trip: The duration of the default 'semiquaver' step. See *Length* below.

Steps

The number of steps used. Note that e.g. a 3-step arpeggio can create a 15-note sequence (or even 24 in *fb* or *bf* loop mode!) if you set Oct to 2 and play a 5 note chord.

Order

Incoming notes are ordered within a **note buffer** in one of two ways. The buffer is then played back in the direction set by the *Loop* parameter (see below).

by note..... notes are reordered according to MIDI note number

as played..... the original order in which notes were played is retained

Octave

0, 1 or 2 times: This switch sets how often the octave is shifted up after all notes in the buffer have been played back.

Loop

The direction the **note buffer** is played back (see *Order* above). The *Loop* setting does not affect the direction of the arpeggiator, which is always forwards, nor does it affect note transposition. See *Transp* on the next page. The options are:

f ==> forwards

b <== backwards

fb <=> forwards / backwards

bf >=< backwards / forwards

Slide

When Slide is switched *On*, any Glide or Glide2 set in the GLOBAL panel will only be applied to connected notes (see Gate below).

Step parameters

The main area of the panel shows the 16 steps, with 5 settings each:

Step

Specifies which note is retrieved from the buffer for this step.

- ▶ play the **next** note
- || play the **same** note
- ◀ play the **first** note (see Order above)
- ▶ play the **last** note (see Order above)

Tip: For typical monophonic arpeggios, set all used steps to **last**.

Length

Step lengths are defined as multiples of the *Arp Sync* value:

- ♪ = 1 x
- ♪ = 2 x
- ♪ = 3 x
- ♪ = 4 x

Gate

As arpeggiators automatically play / release notes, the gate times need to be defined:

- 0, 1, 2, 3, 4.....from very short to almost the length of *ArpSync*
- 5 (arrow)**tie** i.e. connect to the next step (see also *Slide* above)

Note that a tie only connects to the first voice of the following step. If the following step plays multiple voices, these will be triggered.

Voices

The maximum number of notes that can be played simultaneously per step.

Transp

Pitches may be jumping about already, but the individual steps can also be transposed +/-12 semitones... unpredictability is therefore to be expected!

Arp Modulators

The optional bipolar sliders labelled **A** and **B** can be used to modulate any targets (e.g. VCF cutoff and Glide rate) in step with the arpeggiator. For reasons that shall remain a mystery, the corresponding modulation sources are called *ArpMod* and *ArpMod2*.

XY Pad Programming

Click on the XY1 tab in the lower bar...



XY programming panel

Programming the PERFORM pads may seem daunting at first, but it really is quite easy. Especially after following this tutorial:

Quick insight tutorial

Don't enter the PERFORM page yet, stay in the SYNTHESIS page for now.

1. Load *init* by right-clicking on the data display.
2. Right-click on OSC1's Tune knob and select *assign to / X1*.
3. Click on XY1 in the lower bar and see the new assignment there.
4. Click below OSC1 in the grid and select VCF1. Leave the Cutoff at maximum.
5. In the righthand 'Y' area of the XY1 panel, right-click on the topmost 'none' and select Filter1 / Cutoff. Double-click **3 times** on that grey segmented bar to set the limit markers appropriately: Y1 will now span the entire cutoff range, with low values at the bottom and high values at the top.
6. While watching that bar in Y1, move Cutoff up and down in the filter panel. You will see the bar moving in the opposite direction from Cutoff. Leave Cutoff at maximum again.
7. Click on PERFORM, move the handle around the XY1 pad while playing. Watch the movement in the lower area until you understand everything that's happening there. Note that only the lower half of the Y axis affects cutoff...
8. ...so grab the righthand bar and move it to dead center. The data display should read "Filter1 Cutoff, 75.00". If necessary, hold down SHIFT for fine control. Double-click on the bar 3 times to reposition the limit markers.
9. Play with the XY1 pad again. Positive Y values affect cutoff now because **by moving the bar up you turned the cutoff knob down**. Open the SYNTHESIS window and see for yourself, then go back to the PERFORM window.
10. Double-click in the empty field above the pad to the right of the two symbols, enter the text "PITCH & CUTOFF" and click on the Apply button. Next, double-click in the large empty field to the left and enter "X = pitch" and "Y = cutoff" on separate lines. Apply.
11. Try assigning XY2 to other targets e.g. filter resonance and oscillator vibrato. Adjust the triangular limit markers manually instead of double-clicking on the bars this time. You can assign up to 8 targets per axis. You will only see targets for modules that are used in the preset... add more modules and look again!

Controls


X and Y knobs

The 8 knobs in the center mirror the X/Y controls pads in the PERFORM page: Moving a knob will also move the handle in the corresponding pad, and vice versa. Use them to MIDI-learn the X/Y pads for remote control, or for X/Y automation. See [MIDI Learn](#).

Target Selectors and Range Controls

The main area of the XY assignment panel is divided into two blocks: the left half is for the X-axis and the right half is for the Y-axis.

The 16 *Target Selectors* (all set to 'none' by default) open a nested menu containing everything that can be modulated in the current preset. As more modules are added to the grids, more targets will appear. Note that you can use [drag & drop](#) assignment here – simply click on a target selector and drag upwards...



target selectors

*bipolar (top) and unipolar (bottom) range bars
with limit markers (the triangles)*

Targets can also be selected from the SYNTHESIS window or effects panels by right-clicking on a knob and choosing 'assign to / (X1...Y4)' from the context menu.

As soon as a target is selected, a **range bar** representing the full range of the target parameter appears to the right, with a pair of limit markers (the triangles).

Important: In the dead center of this area you will see a vertical line. This represents the current value, and moving the range bar adjusts that value. Go to the SYNTHESIS window and watch the target parameter move in the opposite direction as you slide the range bar left and right. Or vice versa – adjust that knob and watch the range bar.


The two triangular **limit markers** set the minimum and maximum values. You can invert the control by setting the upper marker to the left and the lower one to the right.

Double-clicking on a range bar switches between 3 preset ranges for the limit markers: full range, inverted full range and zero range at the current value.

Configuration



Click on the cogwheel icon at the top righthand corner to open the global configuration pages where you can adjust the UI size and brightness as well as connect Zebra parameters to MIDI continuous controllers. A row of 4 buttons appears:



These are **MIDI Learn** (L), **MIDI Table** (≡), **Preferences** (“tools” symbol) and **Close** (X).
Tip: Right-click anywhere within the row of buttons to set the current page as default.

About MIDI CC

CC, which now officially stands for *Control Change* (no longer *Continuous Controller*) is a multi-purpose message format used for editing and performing presets. CC isn't the only kind of MIDI performance data. For instance, there are different messages for note on/off (including velocity), pitch bend and two kinds of aftertouch.

Although the MIDI Manufacturers Association (MMA) was kind enough to leave most of the 128 CC numbers undefined, two of them have specific meanings that Zebra2 recognizes:

01 = modulation wheel
64 = sustain pedal

Previous versions of Zebra2 also offered the CC controls *Breath* (CC 02) and *Expression* (CC 11). These two have been replaced by user definable CC sources *CtrlA* and *CtrlB*. See the [Preferences](#).

Note that you don't actually need a breath controller (for instance) or an expression pedal to make use of CC messages! Most of the names are purely convention these days – you can use anything that can send a definable CC e.g. some knobs or sliders on your MIDI keyboard, or a controller lane in your MIDI sequencer.

Later MMA revisions to the MIDI spec even included a bunch of esoteric CC definitions such as 'Celeste Detune Depth', probably at the request of a home organ manufacturer or two. We can safely ignore all such definitions.

MIDI Learn



Zebra can be remote-controlled / automated via MIDI messages from a hardware controller unit or from your sequencer program. Click on the configuration button then the **L** to open this view...



The overlay shows all MIDI-learnable elements as selectable outlines. Controls that are already assigned appear filled, like the OSC 1 'Wave', 'Tune' and 'Detune' controls in the above image. The currently active element i.e. the one waiting to be learned is highlighted – like OSC 2 'Wave' here.

Try it: Click on the OSC 1 'Tune' knob and send some MIDI CC data (move a knob or slider on your MIDI controller). The 'Tune' knob becomes opaque and remote-controllable.

The GUI switches (e.g. those in the lower bar) remain active so you can MIDI-learn all parameters without having to exit and switch over.

Tip: If you ever have problems with parameters magically resetting themselves, the usual reason is an *accidental MIDI learn!* Open the **MIDI Table** and have a look...

MIDI Table



Click on the cogwheel and select the [≡] icon to open an editable list of all current MIDI CC assignments:

MIDI table

PITCH & CUTOFF

OSC1

XY3

Parameter	Channel	Controller	Mode	Type	
1 Oscillator1:WaveWarp	1	8	normal	Continuous7bit	✖
2 Oscillator1:Tune	1	7	normal	Continuous7bit	✖
3 Oscillator1:Detune	1	6	normal	Continuous7bit	✖
4 -not assigned-	1	1	normal	Continuous7bit	✖

Parameter

The first field displays/selects one of Zebra's many parameters, which are sorted into sub-menus. Click on the 'Add' button at the bottom and experiment with this option.

Channel / Controller

The next two fields are for MIDI channel and CC number (see *About MIDI CC* above).

Mode

Specifies the range and/or resolution of values:

Normal.....full range, continuous

Integer.....full range, whole numbers only

Fine.....0.01 steps between the two integers closest to the current value

Type

Specifies the output from knobs / sliders on your hardware controller. *Continuous 7bit* is by far the most common, but you should check your hardware specifications anyway:

Encoder127.....'relative mode' endless knobs that repeatedly send the CC value 1 when turned up, or 127 (interpreted as -1) when turned down

Encoder64.....'relative mode' endless knobs that repeatedly send the CC value 65 when turned up, or 63 when turned up

Continuous7bit.....7-bit MIDI CC (normal resolution, common)

Continuous14bit.....14-bit MIDI CC (high resolution, less common)

Removing Assignments

To remove individual assignments, click on the [X] to the right of each line. To remove **all** assignments at once, click on the *Delete All* button at the bottom.

Last Clicked (experimental feature)

Click on the 'Add' button. At the very bottom of the Parameter menu you will see two options called *Last Clicked Control* and *Last Clicked Control Fine*. Select *Last Clicked Control*, enter a suitable controller (MIDI CC) and exit the configuration pages. Which-ever knobs or switches you click on now, the most recent one will respond to that CC! The *Fine* option is similar, but has a very narrow range so you can program a pair of knobs to remote-control anything "coarse" as well as "fine". Work in progress.

Per Instance Control

Control A, Control B

Local versions of the Preference settings *Control A Default* and *Control B Default* (see below). These are not saved with each preset, but per instance with the project.

Preferences



Clicking on the cogwheel then the [TOOLS] icon will open the Preferences window, where you can specify various global settings...

CONTROL

Mouse Wheel Raster

If your mouse wheel is rastered (you can feel slight clicks as you roll it), switch this on and parameter values will increment in 'sensible steps' e.g. integers.

Scroll Horizontal

Folders containing more files than can be shown in the window (e.g. '02 Leads') can be scrolled page-wise via mouse wheel. Opinions differed about the direction, so we made this optional.

APPEARANCE

Default Size

Sets the UI size for each new instance. Note that you can temporarily change the size by right-clicking in the background.

Default Skin

Sets the skin for each new instance (you can temporarily change the skin by right-clicking in the background). The default is 'DotEight', but you might prefer 'DarkEight'.

Gamma


The default brightness.

Text Antialiasing

Smoothing of all labels and values. Usually left on, in rare cases switching this option off can improve readability.

Wavefolder Graph

Appearance of the FOLD module's graph: *eco*, *fast* or *glow*, in order of CPU usage.



PRESETS

Auto Versioning

If this option is switched on, an index is appended to the preset name and automatically incremented each time you save it. For instance, saving 'Space' three times in a row would give you three files: 'Space', 'Space 2' and 'Space 3'.

Save Presets To

Choosing 'user folder' here causes all saved presets to land in the *User* folder instead of the currently selected one.

Scan On Startup

Whether the preset library should be scanned and the database recreated when the first instance of Zebra2 is started, e.g. when you reopen a project.

AUDIO

Base Latency

Only disable this option if you are 100% sure that your audio system – hardware as well as software – uses buffers that are a multiple of 16 samples. Otherwise you should leave it at '16 samples' to prevent crackles.

Note that a new Base Latency setting will only take effect when the host allows e.g. on playback or after switching the sample rate. Reloading Zebra2 will always work.

ABOUT THOSE BUFFERS

Internally, Zebra processes audio in chunks of $n \times 16$ samples. This so-called 'block processing' method significantly reduces CPU load and memory usage.

For instance, if the number of samples to be processed is 41, Zebra will process the first 32 and keeps the remaining 9 in a small buffer (16 samples is enough). Those 9 samples are then processed at the start of the next call.

Note: The extra buffer is only necessary if either the host or the audio driver is processing "unusual" buffer sizes. In the many host applications that process buffers of 64, 128, 256 or 512 samples (all multiples of 16), try switching it off so that Zebra can process latency-free.

Control A/B Default

The list of modulation sources in earlier versions of Zebra2 included the fixed MIDI CC *Breath* (CC#02) and *Xpress* (expression pedal, CC#11). Since version 2.8 we have replaced these with the user-definable CC sources *CtrlA* and *CtrlB*, retaining *Breath* and *Expression* as the default CC to ensure compatibility with older presets.


MIDI Control Slew

The strength of parameter smoothing for all performance control sources: *PitchW* (pitch wheel), *ModWhl* (modulation wheel), *CtrlA*, *CtrlB* as well as *ATouch* (aftertouch i.e. channel pressure or poly pressure). The default setting is 'fast'.


Tips & Tricks

Motion viewer for modulators


Thanks to Brian Rzycki for this tip: Load *init* then assign MMap1 as modulation source for something, e.g. Lane 1 Pan (the target doesn't actually matter for this experiment). A modulation mapper will appear in the modulators panel:



Change the MODE to *Map Smooth*. Select LFO1 as MODULATOR (it's unfortunate that we can't select MMix1 here!) Click on the window icon to expand the map, set the extreme left and right values both to maximum, right-click and select *Straighten*. CLOSE the expanded map. It should now look like this:



Play a note and turn down the LFO rate (this trick only works well if the modulator is relatively slow). Also works fine with envelopes or MIDI input such as *aftertouch*.



Spectralize


The modulation mappers' context menu includes a function inherited from u-he synths that can use the maps as audio waveforms (e.g. ACE, Bazille): Spectralize interprets the map as the first 128 partials of the harmonic series, then converts the data into the actual waveform. In Zebra, this is an easy way to create a smooth, complex curve.

Try this: Load *init*, click on the OSC1's Tune modulation knob and select *MMap1*. Right-click in MMap1 and select *Reset*. Right-click again and restrict the size of the map to 5. Move those 5 values up or down, right-click once more and select *Shapes / Spectralize...*

To scan in one direction only, set the waveform of the modulator (LFO2 here) to *saw up*.


Modulation inverter

It is sometimes necessary to invert unipolar modulation sources, for instance if you want to cross-fade between two lanes of the main grid. Here's how to do that:



Alternatively, a Mix module can cross-fade between two signals **at source** e.g. individual oscillator volumes. However, the solution here is generally more flexible as it can convert unipolar to bipolar and lets you create non-linear curves.

Absolute value



This example always outputs positive pitch wheel values - a minus times a minus is a plus.

Vibrato under control



When the mod-wheel is at minimum, output is all *ATouch*, and when at maximum, output is all *ModWhl* – so the sum of the sources always adds up to 100%.

Especially 'Prog-Rock' keyboard wizards will understand the reason for this one. It lets you add vibrato using either modulation wheel or aftertouch or any mixture of the two in the same preset, without letting vibrato get too deep. So you can take that solo using the wheel, then get back to playing two keyboards at once and use aftertouch instead.

More MSEG points

If you really need more points than the 33 available in each MSEG, try using a couple of MSEGs in series. Here's how: Extend the very last segment of the first MSEG to the total length of the second MSEG, then extend the first segment of that MSEG to the length of the first MSEG minus that long segment. Add them together using a modulation mixer.

Zebrify

Introduction

The 'effects' version of Zebra2. Zebrify includes several features that transcend what you would normally expect from an insert effect, for instance audio oscillators. With carefully programmed pitch-detection, Zebrify can even be used as a powerful guitar synthesizer! Like the effects section in Zebra2, Zebrify is not polyphonic but 'single voice'.



Zebrify's Synthesis window, showing all generator and effect modules in a single grid

Zebrify uses the main patching grid for all modules. It has fewer of these than Zebra2...

VCF (4)	Ring (1)	Rev (1)	Dist (1)
FMO (2)	XMF (2)	Comp (2)	Fold (1)
Comb (2)	SB (2)	EQ (2)	NuRev (1)
Shape (2)	ModFX (2)	OSC (2)	
Mix (2)	Delay (2)	Noise (2)	

...but includes four extra modulation sources:

EnvFol1	Pitchness	Essness	Transient
---------	-----------	---------	-----------

Note: Zebrify's equivalent of *KeyFol* is called *PitchTrk* (pitch tracking).

MIDI

Click on the 'Midi' tab in Zebrify's lower bar to open this panel:



Zebrify's MIDI panel, with KeySource menu

Together with the Pitch Detector (see a few pages down), this panel is mainly concerned with Zebrify's own monophonic version of **KeyFol**, the key-follow modulation source.

Important: Several DAWs (e.g. Cubase and Reaper) automatically route MIDI into insert effects. Others, however, use more complicated methods – you might have to spend some time searching in the appropriate documentation for information on how to do this!

Glide

Smooths KeyFol when KeySource is set to 'MIDI'...

KeySource

Determines how Zebrify derives its note data i.e. KeyFol and envelope gate.

MIDI.....KeyFol uses incoming MIDI notes with last note priority, like in Zebra2's effects section. Envelopes and MSEGs can only be triggered in this mode.

Input.....Detects the pitch, KeyFol is a continuous variable.

In Qtz.....Detects the pitch, KeyFol is quantized to the nearest semitone.

Output

Zebrify's main output level control.

Keyboard

Displays detected or MIDI notes (see *KeySource* above). Notes derived from input signals with ambiguous pitch content (e.g. chords) can cause the keys to jump wildly.

The keyboard can also be used to trigger/gate envelopes and MSEGs manually (especially useful if your sequencer is incapable of routing MIDI data into effect plugins).

Input

Click on the 'Input' tab in the lower bar. The input pane contains three panels: Input Mixer, Envelope Detector and Pitch Detector...

Input Mixer

Zebrify's grid has four lanes, and each has its own input...



Zebrify's Input Mixer panel

Input1 ... Input4

Input levels. Input1 goes to the lefthand lane of the grid, Input2 to the next lane etc..

Input selectors

Stereo, *left*, *right* or *mono-sum* for each input. For instance, setting Input1 to 'left' and Input2 to 'right' lets you split the two channels of a stereo signal between lanes 1 and 2.

Envelope Detector

The Envelope Detector continuously analyses the input signal level and outputs the modulation source **EnvFol1** (envelope follow). EnvFol1 can then be used to control targets that would typically be modulated by a standard envelope e.g. the output level of a lane in the grid. Note that envelope detection is independent of the Input Mixer settings.



Zebrify's Envelope Detector panel

MODE

FollowEnvFol1 is an envelope follower, proportional to input signal level

AR Env.....EnvFol1 is an Attack-Release envelope triggered at the Threshold

CURVE

linear.....EnvFol1 is linear – good for modulating levels e.g. lane volumes

exponential.....EnvFol1 is exponential – for modulating frequencies e.g. filter cutoff

Attenuation

Gain control for the envelope detector only, independent of Input Mixer levels. See also *Threshold* below.

Attack

Rise time after the signal level has reached the threshold (see *Thresh* below).

Release

Fall time after the signal level drops below the threshold.

VU

Input level display.

LVL (level)

Realtime display of EnvFol1 output level.

Threshold

This knob adjusts the level at which the envelope follower is 'on'. Use together with the *Attenuation* parameter (see above).

Smooth

Smooths both Attack and Release.

FILTER TYPE

Zebrify's envelope detector includes an input filter so it can be set up to react to certain frequencies only. See *Filter* below.

signalNo filter

bandpass.....Isolate a particular frequency

lowpassIsolate low frequencies e.g. bass drum


highpass.....Isolate high frequencies e.g. hi-hat

Filter

Cutoff frequency of the envelope detector's input filter.

Pitch Detector

Input signals with a strong fundamental can be used to control the pitch of Zebrify's oscillators. Patch up your own guitar synthesizer or voice-controlled 'Theremin'.



Zebrify's Pitch Detector panel

MODE

percussive.....for strong attack signals: acoustic guitar, tuned percussion etc.

voicedfor breathy / noisy signals: vocals, flutes etc.

clearfor mostly pure signals: monophonic synth lines etc.

SOURCE

Input selector for pitch detection – *stereo*, *left*, *right* or *monosum*.

Sense (Input)

The main input gain for all parts of the Pitch Detector, with an indicator that lights up whenever the signal is strong enough for pitch detection.

TRANSIENT Decay

Controls how quickly **Transient** decays to zero.

TRANSIENT Sense

This threshold determines the level at which transients (short-lived jumps in volume) will be recognized as such. The output of this section is the **Transient** modulation source...

ESS on/off switch

Adds detected transients to the **Ess** modulation source. See ESS Sense.

ESS Sense

Ess frequency cutoff, from 4 to 8 kHz ('esses' are sibilants, high-frequency noises with little or no pitch content). The output of this section is the **Essness** modulation source.

PITCHNESS Sense

The opposite of Essness – it reacts to pitched signals. Set low values for meticulous but slow pitch detection, and higher values for signals with clear pitch content. The output is the **Pitchness** mod source, a smooth gate that opens as long as pitch is detected.

PITCH HiNote, LowNote

Limits pitch detection to a range of notes (standard MIDI note numbers).

ZRev

Despite its austere appearance, ZRev is the mother of non-convolution reverb units. It is a tool for hand-tuning delay coefficients in feedback delay and allpass networks. Exactly how it works is a well-kept secret – to quote Urs Heckmann:

“Before tweaking any knob on Zrev one should google the following terms: *comb allpass filter*, *feedback delay network*, *jot householder matrix*, and *schroeder moorer reverb*.”



Assuming you didn't just spend hours searching those words, the following should help: The left section is a feedback delay network with damping, and the right section is two cascades of nested allpass filters with adjustable feedback for each set.

ZRev is a challenge. If enough people try enough different coefficients for a long enough time, somebody might just stumble upon a great-sounding set. The ZRev challenge should not be seen as a “chimps on typewriters” scenario – in theory, ZRev is capable of emulating any artificial reverb, and it's up to you to work out the best strategy! However...

The relative values affect the room quality – the more irregular, the better. Some claim that prime numbers or other special ratios are necessary, but so far the best tactic still appears to be simple trial-and-error. If you have a set of values that produces zero metallic ringing, please contact anybody@u-he.com immediately!

Although ZRev itself has no Save button, you can save your settings in the native format of the host application (there should be a Save button somewhere at the top of the window).

Note: Right-clicking on knobs lets you MIDI-Learn “the old way” for remote control via CC. Select “MIDI Learn” and move a hardware control that is sending MIDI CC to ZRev.

Modulation Target Lists

Generators

Target names are in alphabetical order. Knob names are in **bold**. “Modulation amount” means the degree to which another modulator affects its target.

OSC	
Tune	Tune in semitones
Key Scale Pitch	KeyS (lower panel)
TuneModDepth	(assignable) Tune modulation amount
Phase	Phase/PW
PhaseModDepth	(assignable) Phase modulation amount
WaveWarp	Wave index
WarpModDepth	(assignable) Wave modulation amount
Vibrato	Vibrato
SpectraFX1 Val	spectral effect 1 value
SFX1ModDepth	(assignable) spectral effect 1 modulation amount
SpectraFX2 Val	spectral effect 2 value
SFX2ModDepth	(assignable) spectral effect 2 modulation amount
Detune	Detune
Volume	Volume
VolumeModDepth	(assignable) Volume modulation amount
Pan	Pan
PanModDepth	(assignable) Pan modulation amount
SyncTune	Sync
SyncModDepth	(assignable) Sync modulation amount
Poly Width	Width (for dual, quad, eleven)
Normalize	Normalize (lower panel)

Noise	
Filter1	LP Cutoff (lowpass)
F1 ModDepth	(assignable) Lowpass modulation amount
Filter2	HP Cutoff (Highpass)
F2 ModDepth	(assignable) Highpass modulation amount
Volume	Volume
VolumeModDepth	(assignable) Volume modulation amount
Pan	Pan
PanModDepth	(assignable) Pan modulation amount
Width	Width

VCF	
Cutoff	Cutoff
Resonance	Res
Drive *	Drive / Vowel / Split
Gain *	Gain
ModDepth1	(assignable) Cutoff modulation amount 1
ModDepth2	(assignable) Cutoff modulation amount 2
KeyFollow	KeyF

* depending on filter Type

FMO	
Tune	Tune in semitones
Key Scale Pitch	Key Scale Pitch (lower panel, unlabelled horizontal slider)
TuneModDepth	(assignable) Tune modulation amount
FM Depth	FM
FM ModDepth	(assignable) FM modulation amount
Vibrato	Vibrato
Detune	Detune
Volume	Volume
VolumeModDepth	(assignable) Volume modulation amount
Pan	Pan
PanModDepth	(assignable) Pan modulation amount
Width	Width

Comb	
Tune	Tune (semitones)
key scale	KeyScale
TuneModDepth	(assignable) Tune modulation amount
Detune	Detune
Vibrato	Vibrato
Feedback	Feedbk
FBModDepth	(assignable) Feedback modulation amount
Damp	Damp
DampModDepth	(assignable) Damp modulation amount
PreFill	PreFill
Input	Input
InputMod	(assignable) Input modulation amount
Tone	Tone
ToneMod	(assignable) Tone modulation amount
Flavour	Flavour
FlavourMod	(assignable) Flavour modulation amount
Distortion	Distortion
Dry	Dry
Volume	Volume
VolumeModDepth	(assignable) Volume modulation amount
Pan	Pan
PanModDepth	(assignable) Pan modulation amount
Width	Width

Shape	
Depth	Depth
D_modDepth	(assignable) Depth modulation amount
Edge	Edge
Edge ModDepth	(assignable) Edge modulation amount
Input	Input
Output	Output
HiOut	HiOut

Mix (ChannelMix)	
Pan	Pan
Mix	Mix
PanMod Depth	(assignable) Pan modulation amount

XMF	
Cutoff	Cutoff
Resonance	Res
Freq mod1	(assignable) Cutoff modulation amount 1
Freq mod2	(assignable) Cutoff modulation amount 2
KeyFollow	KeyF
FreqOffset	Offset
FreqOffMod	(assignable) Offset modulation amount
FilterFM	FM
XFMmod	(assignable) FilterFM modulation amount
Overload	Over
Click	Click

SB	
Frequency	Freq
FModDepth	(assignable) Freq modulation amount
Offset	Offset
OModDepth	(assignable) Offset modulation amount
Mix	Mix
MModDepth	(assignable) Mix modulation amount

Distortion	
Input	Input
Output	Output
Pre Tilt	Pre Tilt
Post Tilt	Post Tilt
Center Freq	Center Freq
Low	Low
High	High

Fold	
Folds	Folds
Fold Mod	(assignable) Fold modulation amount
Bias	Bias
Bias Mod	(assignable) Bias modulation amount
FoldRatio	Ratio
FoldSlope	Slope
Clip Angle	Clip Angle

Voice Circuit	
Portamento	Glide (GLOBAL/GLIDE panel)
Portamento2	Glide2

Modulators

Envelopes	
Init	(assignable) Initial level before the Attack stage
Attack	Attack
Decay	Decay
Sustain	Sustain level
Fall/Rise	F/R
Sustain2	(assignable) Sust2 level (if Sust2 is active)
Release	Release
Velocity	Vel
Vel2I	Velocity Scale initial level amount (if Init is active)
Vel2A	Velocity Scale to Attack amount
Vel2D	Velocity Scale to Decay amount
Vel2S	Velocity Scale to Sustain amount
Vel2FR	Velocity Scale to F/R amount
Vel2S2	Velocity Scale to Sust2 amount (if Sust2 is active)
Vel2R	Velocity Scale to Release amount
Key2I	Key Scale to initial level amount (if Init is active)
Key2A	Key Scale to Attack amount
Key2D	Key Scale to Decay amount
Key2S	Key Scale to Sustain amount
Key2FR	Key Scale to F/R amount
KeyS2	Key Scale to Sust2 amount (if Sust2 is active)
Key2R	Key Scale to release amount
Slope	Slope (if the envelope is in v-slope mode)

MSEGs	
Velocity	Velocity amount
Attack	Attack time
Loop	Loop time
Release	Release time

LFO	
Phase	Phase
Rate	Rate
Amplitude	Amp
Delay	Delay
DepthMod Dpt1	(assignable) Amp modulation amount
FreqMod Dpt	(assignable) Rate modulation amount

MMix	
Constant	CON

Voice Mix	
Pan1	PAN (in lane mixer)
Pan Mod Dpt1	MOD (in lane mixer) = assignable pan modulation depth
Volume1	VOL (in lane mixer)
Mod Depth1	MOD (in lane mixer) = assignable volume modulation depth
etc.. for lanes 2-4	
Send1	Send1 (in GLOBAL / centre panel)
SendDepth1	(assignable) Send1 modulation amount
Send2	Send2
SendDepth2	(assignable) Send2 modulation amount

Global

LFOG (LfoG)	
Phase	Phase
Rate	Rate
Amplitude	Amp

Master	
Return1	BUS 1
Return2	BUS 2
Master	MAIN

Effects

ModFX	
Center	Center
Speed	Speed
Stereo	Stereo
Depth	Depth
Feedback	Feedbk
Mix	Mix
LowCut Freq	Low Freq
HiCut Freq	High Freq
Quad	Quad
QuadPhase	Q-Phase
Low Boost dB	Boost (low)
High Boost dB	Boost (high)

Delay	
Mix	Mix
Feedback	Feedback
X-Back	X-back
Lowpass	Lowpass
Hipass	Hipass
Ratio1 ... Ratio4	Ratio 1 ... Ratio 4
Pan1 ... Pan4	Pan 1 ... Pan 4

Shape	
Depth	Depth
D_modDepth	(assignable) Depth modulation amount
Edge	Edge
Edge ModDepth	(assignable) Edge modulation amount
Input	Input
Output	Output
HiOut	HiOut

Mix (ChannelMix)	
Pan	Pan
Mix	Mix
PanMod Depth	(assignable) Pan modulation amount

Reverb	
Dry	Dry
Wet	Wet
Feedback	Feedback
Damp	Damp
Range	Range
Speed	Speed
Modulation	Modulation
Diff Feedback	D-Feedb
Diff Range	D-Range
Diff Mix	D-Mix
Diff Mod	D-Mod
Diff Speed	D-Speed
PreDelay	PreDelay

Comp	
Compression	Comp
Threshold	Threshold
Attack	Attack
Release	Release
Input	Input
Output	Output

EQ (Equalizer)	
Freq LowShelf	(1) horizontal position
Q LowShelf	(1) slope
Gain LowShelf	(1) vertical position
Freq Mid1	(2) horizontal position
Q Mid1	(2) slope
Gain Mid1	(2) vertical position
Freq Mid2	(3) horizontal position
Q Mid2	(3) slope
Gain Mid2	(3) vertical position
Freq HiShelf	(4) horizontal position
Q HiShelf	(4) slope
Gain HiShelf	(4) vertical position

VCF	
Cutoff	Cutoff
Resonance	Res
Drive *	Drive / Vowel / Split
Gain *	Gain
ModDepth1	(assignable) Cutoff modulation amount 1
ModDepth2	(assignable) Cutoff modulation amount 2
KeyFollow	KeyF

* depending on filter Type

SB	
Frequency	Freq
FModDepth	(assignable) Freq modulation amount
Offset	Offset
OModDepth	(assignable) Offset modulation amount
Mix	Mix
MModDepth	(assignable) Mix modulation amount

XMF	
Cutoff	Cutoff
Resonance	Res
Freq mod1	(assignable) Cutoff modulation amount 1
Freq mod2	(assignable) Cutoff modulation amount 2
KeyFollow	KeyF
FreqOffset	Offset
FreqOffMod	(assignable) Offset modulation amount
FilterFM	FM
XFMmod	(assignable) FilterFM modulation amount
Overload	Over
Click	Click

Distortion	
Input	Input
Output	Output
Pre Tilt	Pre Tilt
Post Tilt	Post Tilt
Center Freq	Center Freq
Low	Low
High	High


NuRev	
Pre-Delay	PreDelay
Damp	Damp
Decay	Decay
Size	Size
Tone	Tone
Width	Width
Dry/Wet Mix	Dry/Wet
Pan	(hidden parameter – no visible control)

Flow Diagrams


Delay Modes



See [Delay1 / Delay2](#) on page 72. Thanks to Ed Harvey for the originals of these diagrams!

stereo 2



multitap 4




dubby 2+2**serial 2**


XMF Modes

See [XMF](#) on page 47.


single




serial



parallel




diff'd



The only difference between the *parallel* and *diff'd* modes is that in *diff'd*, the F2 signal is subtracted from F1 instead of added to it.

FX Grid

See [The FX Grid](#) on page 70.



NKS

This version supports Native Instruments **NKS** format so that Zebra2 can be integrated into the Komplete Kontrol or Maschine environments. The factory presets are (optionally) also installed as tagged *.nks* files. A few pages of performance controls mapped to common parameters are automatically generated and saved together with each *.nks* preset.

Saving as .nks is only possible in the VST2 version

Mac owners can use (temporarily) if necessary – any host that supports VST2

Saving in NKS format

While the native, h2p and h2p extended options cause Zebra2 to save presets into the currently selected preset directory, *.nks* files go directly into the preset location used for Komplete Kontrol or Maschine, so they do not appear in Zebra2's preset browser. To make them visible in Komplete Kontrol, open its preferences and rescan the preset locations.

Batch conversion

Right-click the [SAVE] button and set the target format to *nks*. Via cmd-click (Mac) or alt-click (Win), select all presets in the current folder you want to convert, then right-click any of the selected presets and choose *convert to nks*. The original files are not affected.

What to do if Zebra2 doesn't appear in Komplete Kontrol / Maschine.

First, make sure your NKS software is up to date: Komplete Kontrol V1.5+ or Maschine V2.4 are the minimum requirements for u-he. In Windows, Komplete Kontrol must know the *Vstplugins* folder containing Zebra2: Open the Komplete Kontrol preferences, go to Locations and add your *Vstplugins* directory if necessary, hit Rescan and check whether Zebra2 appears. Maybe the NKS preset folder is empty? If so, please reinstall Zebra2 with the correct VST path and the NKS-option checked. Here are the preset folder locations:

Mac *Macintosh HD/Library/Application Support/u-he/Zebra2/NKS/Zebra2/*

Win *C:\Users*YOU*\Documents\u-he\Zebra2.data\NKS\Zebra2*

Perhaps the XML-File is missing from this location:

Mac *Macintosh HD/Library/Application Support/Native Instruments/Service Center/u-he-Zebra2.xml*

Win *C:\Program Files\Common Files\Native Instruments\Service Center\u-he-Zebra2.xml*

A re-install with the NKS-option checked should also remedy this issue.

What to do if Komplete Kontrol / Maschine is unable to load Zebra2

Either the VST2 version of Zebra2 wasn't installed, or the path wasn't correct.

Mac *Macintosh HD/Library/Audio/Plug-Ins/VST/u-he/*

Win *<User VST Folder> / (path as set for the VST plug-in during installation)*

If Zebra2's VST plug-in cannot be found in these locations you should run the installer again, making sure that you set the correct path and activate 'VST' during installation.

Troubleshooting

Random Notes

Problem

Zebra goes “out of tune” after 10 to 15 minutes.

Solution

That’s Zebra’s demo-mode restriction! Reload the plug-in or purchase a license.

Parameter Reset

Problem

“I’m on [computer platform and OS version] using [DAW]. I load Zebra2 into a project, and whenever I play the song or try to record, it resets [parameter] to [value]”.

Solution

That sounds like an unwanted MIDI learn – a controller has somehow been assigned to that parameter, and restarting the song resets all assigned controllers. Simply remove the offending connection from the [MIDI Table](#).

Note: MIDI Learn assignments are global for all presets in all instances of Zebra2, and are stored at the following locations:

Win

`C:\Users\[you]\Documents\u-he\Zebra2.data\Support\com.u-he.Zebra2.midiassign.txt`

Mac

`~/Library/Application Support/u-he/com.u-he.Zebra2.midiassign.txt`

NKS troubles

Please refer to the previous page, and contact Native Instruments’ support if necessary.

If all else fails, there’s our online support at www.u-he.com. Not open at weekends, but otherwise fairly quick to respond!

The End